

BAYSIDE SURVEYING

11765 HWY 101 South
Tillamook, Oregon 97141

Terry L. Jones
503-842-5551
Fax 503-842-5552

October 2002

REWITNESS
SECTION CORNER COMMON TO SECTIONS 25, 36 & 31
TOWNSHIP 2 SOUTH, RANGE 8 and 7 WEST
(East line of Township 2 South, Range 8 West)

I found:

48" rotten Hemlock stump bears N29°W 19.1' (GLO 24" Hemlock bears N39°W 29 lks);

24" rotten Hemlock stump bears N39°E 27.7' (GLO 8" Hemlock bears N39°E 42 lks);

40" rotten Hemlock stump bears S54°E 35.0' (GLO 16" Hemlock bears S54°E 53 lks);

East-West creek is North 99' (GLO E-W creek 1.5 chains North of corner);

I set 1½" X 40" galvanized iron pipe with SODF brass cap stamped "T2SR8W S25 S36 S31 R7W 2002 LS2507" flush with ground.

From which:

Set Steel posts North 4' and South 4', and 4 New BTs as follows:

11" Douglas Fir scribed "T2S R8W S25 BT" bears N11°W 22.70' to brass nail and washer stamped "LS2507" between the B & T;

12" Douglas Fir scribed "T2S R8W S36 BT" bears S78°W 6.57' to brass nail and washer stamped "LS2507" between the B & T;

16" Douglas Fir scribed "T2S R7W S31 BT" bears S75°E 5.18' to brass nail and washer stamped "LS2507" between the B & T;

In the presence of Terry Jones, Dallas Esplin

