

BAYSIDE SURVEYING

11765 HWY 101 South
Tillamook, Oregon 97141

Terry L. Jones
503-842-5551
Fax 503-842-5552

October 2002

REWITNESS

SECTION CORNER COMMON TO SECTIONS 25, 26, 35 & 36
TOWNSHIP 2 SOUTH, RANGE 8 WEST

I Found:

No evidence of any original GLO bearing trees or stone. Area appears to be heavy logged (creek is full of logs and there is a cat road 50 feet above the corner. I set corner holding topo calls to North and East, see map. This solution also fits topo calls of ridge and creek to South and is nearly on line with corners to South and North.

Small creek running S20°E is 6.6' East (GLO at 0.10 chains, "Creek, 3 lks. wide, runs S20°E);

Small creek running SE is 66' North (GLO at 1.00 chains, "Brook, 2 lks. wide, runs SE.");

Ridge running S15°E is 528' East (GLO at 8.00 chains, "Top of ridge, bears" S15°E).

I set 1½" X 40" galvanized iron pipe with SODF brass cap stamped "T2SR8W S26 S25 S35 S36 2002 LS2507" flush with ground.

From which:

Set steel posts 4' North, South, East and West, and 4 New BTs as follows:

10" Alder bark scribed "T2S R8W S25 BT" bears N60°E 29.3' to brass nail and washer stamped "LS2507" between the B & T;

12" Alder bark scribed "T2S R8W S26 BT" bears N24°W 28.1' to brass nail and washer stamped "LS2507" between the B & T;

18" Douglas Fir scribed "T2S R8W S35 BT" bears S89°W 62.8' to brass nail and washer stamped "LS2507" between the B & T;

12" Alder bark scribed "T2S R8W S36 BT" bears S2°E 19.5' to brass nail and washer stamped "LS2507" between the B & T;

In the presence of Terry Jones, Dallas Esplin

