

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT
Tillamook County Surveyor's Office

SECTION: 29 & 30 TOWNSHIP: 3 South RANGE: 9 West

COUNTY: Tillamook DATE: 4/2022

CORNER DESIGNATION: South Sixteenth corner of Sections 29 and 30, Township 3 South, Range 9 West; Willamette Meridian.	(Please check one)	
	<input type="checkbox"/>	Condition Report Only
	<input type="checkbox"/>	Restoration
	<input type="checkbox"/>	Rewitness
	<input type="checkbox"/>	Unrecorded
	<input checked="" type="checkbox"/>	Reset at surface
<input type="checkbox"/>	Referenced Out	

Previous Rewitnesses, Restorations and Surveys, etc... A-234, A-247, A-264 (1946), A-382, A-823 (1959), A-1025 (1967), A-1220 (1965), A-1505 (1967), A-1540 (1968), A-1885 (1969), A-2591 (1973), A-3103 (1977), A-3777 (1979), A-3960 (1979), A-4161 (1980), A-4169 (1983), A-4869 (1983), A-5135 (1984), A-5852 (1989), A-6136 (1991), A-7671 (2001), A-7779 (2002), A-8271 (2008), B-305, B-591, B-1087 (1983), B-1778 (1994), B-2464 (2001), B-2585 (2002), B-2627 (2003), B-2633 (2003), B-4043 (2020), S3 PG. 166 (1899), F40-56 (1913), Rewitness Bk. 5 pg. 212 (1966), Rewitness card # 555 (1971), P-401 (1997), P-598 (2000), P-608 (2000), P-630 (2001), P-650 (2001), P-716 (2003), Rewitness Bk. 8 pg. 43 (2015)

History, condition, and sources: The monument for the South 1/16th corner of Sections 29 and 30 was first set by U. G. Jackson (F40-56) in 1913. He set a galvanized iron pipe for the monument. In 1959 (A-823) The sixteenth corner was reported to be a pipe. There is no description of the corner recorded from 1959 until 1966 (Rewitness Bk. 5 pg. 212) the Tillamook County Surveyors office found a 3/4" iron bar flush with blacktop and they set 4 new accessories. In 1971 (Rewitness # 555) The Tillamook County Surveyors office found the iron bar and placed 1.25" rebar with centerpunch over existing found iron bar no new accessories were set. In 2015 the Tillamook County Surveyors office found 1.25" centerpunched rebar .30' below surface of the road and set one new accessory. In 2021 Tillamook County Surveyors office had the Tillamook County public works install 6" metal sleeve while paving around the found South 1/16th corner a centerpunched 1.25" rebar .6' below surface and added a 3" Tillamook County Brass cap with 1.25" rebar stem over the existing monument anchored in concrete and stamped as shown hereon.

Not Found: (Rewitness Bk. 8 pg. 43) power pole North 72° West 34.95'
 Not Found: (Rewitness Bk. 8 pg. 43) flagpole South 22° West 110.10'
 Found: (Rewitness Bk. 8 pg. 43) yellow metal location tag on galvanized fence post South 34.8'

New : Set a 3" Tillamook County Brass Cap with a 6" long by 1.25" rebar stem in a 6" metal sleeve with anchoring cement flush with the surface of the pavement stamped as shown hereon. The new monument was set over the found 1.25" center punched rebar using a tripod with a laser plumet attached; set up directly over the old monument and centered on the dimple of the existing monument. Anchoring cement was then mixed up and the monument was set in the concrete and aligned using the laser plumet. Position was verified by performing a direct static GPS tie.

The Monument was tied directly using GPS established control. The coordinates have been converted and are provided here in WGS 84, Latitude and Longitude.

Latitude: 45° 16' 37.09"
 Longitude: - 123° 49' 28.71"



Location: ±367' East from the intersection of Hwy 101 and Beaver-Blaine Rd. and ±5.5' North of painted centerline of Beaver-Blaine Rd.

Tillamook County Surveyor office: 1510 3rd Street Suite C, Tillamook, OR. 97141

Party Chief: Terry Jones, P.L.S. 2507, Survey Supervisor

Witnesses: Michael Rice, P.L.S. 86926, Tillamook County Surveyor
 Travis Porter, Survey Tech.

Notes: Digital images taken of monument and accessories.

SURVEYOR'S SEAL

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Michael R. Rice

OREGON
 DECEMBER 11, 2012
 MICHAEL R. RICE
 86926
 RENEWAL 12-31-2022

