Tillamook County

DEPARTMENT OF COMMUNITY DEVELOPMENT BUILDING, PLANNING & ON-SITE SANITATION SECTIONS



Land of Cheese, Trees and Ocean Breeze

1510 – B Third Street Tillamook, Oregon 97141 www.tillamookcounty.gov (503) 842-3408

Floodway Development Permit #851-24-000580-PLNG: MCREYNOLDS/SPATH

NOTICE TO MORTGAGEE, LIENHOLDER, VENDOR OR SELLER: ORS 215 REQUIRES THAT IF YOU RECEIVE THIS NOTICE, IT MUST BE PROMPTLY FORWARDED TO THE PURCHASER

NOTICE OF ADMINISTRATIVE REVIEW Date of Notice: April 11, 2025

Notice is hereby given that the Tillamook County Department of Community Development is considering the following:

<u>851-24-000580-PLNG</u>: A review of a Floodway Development Permit for the placement of a proposed single-family dwelling near the Nestucca River. The subject property is accessed from Airport Way, a County local access road, and is designated as Tax Lot 6100, of Section 30BD of Township 4 South, Range 10 West of the Willamette Meridian, Tillamook County, Oregon. The property is located in the Pacific City/Woods Medium Density Residential (PCW-R2) Zone. The applicant is Ian Spath and the property owner is Pacific City Property Trust/Mali Ann McReynolds.

Written comments received by the Department of Community Development prior to 4:00p.m. on April 25, 2025, will be considered in rendering a decision. Comments should address the criteria upon which the Department must base its decision. A decision will be rendered no sooner than the next business day, April 28, 2025.

Notice of the application, a map of the subject area, and the applicable criteria are being mailed to all property owners within 250 feet of the exterior boundaries of the subject parcel for which an application has been made and other appropriate agencies at least 14 days prior to this Department rendering a decision on the request.

A copy of the application, along with a map of the request area and the applicable criteria for review are available for inspection on the Tillamook County Department of Community Development website: https://www.tillamookcounty.gov/commdev/landuseapps and is also available for inspection at the Department of Community Development office located at 1510-B Third Street, Tillamook, Oregon 97141.

If you have any questions about this application, please call the Department of Community Development at 503-842-3408 Ext. 3315 or lynn.tone@tillamookcounty.gov.

Sincerely.

Melissa Jenck, CFM, Senior Planner

Sarah Absher, CFM, Director

Enc. Applicable Ordinance Criteria, Maps

REVIEW CRITERIA

ARTICLE III – ZONE REGULATIONS


TCLUO SECTION 3.510: FLOOD HAZARD OVERLAY ZONE

- (1) The fill is not within a Coastal High Hazard Area.
- (2) Fill placed within the Regulatory Floodway shall not result in any increase in flood levels during the occurrence of the base flood discharge.
- (3) The fill is necessary for an approved use on the property.
- (4) The fill is the minimum amount necessary to achieve the approved use.
- (5) No feasible alternative upland locations exist on the property.
- (6) The fill does not impede or alter drainage or the flow of floodwaters.
- (7) If the proposal is for a new critical facility, no feasible alternative site is available.
- (8) For creation of new, and modification of, Flood Refuge Platforms, the following apply, in addition to (14)(a)(1-4) and (b)(1-5):
 - i. The fill is not within a floodway, wetland, riparian area or other sensitive area regulated by the Tillamook County Land Use Ordinance.
 - ii. The property is actively used for livestock and/or farm purposes,
 - iii. Maximum platform size = 10 sq ft of platform surface per acre of pasture in use, or 30 sq ft per animal, with a 10-ft wide buffer around the outside of the platform,
 - iv. Platform surface shall be at least 1 ft above base flood elevation,
 - v. Slope of fill shall be no steeper than 1.5 horizontal to 1 vertical,
 - vi. Slope shall be constructed and/or fenced in a manner so as to prevent and avoid erosion.

Conditions of approval may require that if the fill is found to not meet criterion (5), the fill shall be removed or, where reasonable and practical, appropriate mitigation measures shall be required of the property owner. Such measures shall be verified by a certified engineer or hydrologist that the mitigation measures will not result in a net rise in floodwaters and be in coordination with applicable state, federal and local agencies, including the Oregon Department of Fish and Wildlife.


EXHIBIT A

Vicinity Map




Zoning Map





Generated with the GeoMOOSE Printing Utilities



Tillamook County 2024 Real Property Assessment Report

Account 240821

Map

4S1030BD06100

Tax Status

Assessable

Code - Tax ID

2202 - 240821

Account Status Subtype

NORMAL

Active

Legal Descr

RIVERGATE

Block - 2 Lot - 5

Mailing

MCREYNOLDS, MALI ANN TRUSTEE

PO BOX 305

PACIFIC CITY OR 97135

Deed Reference # 2023-2339

Sales Date/Price

05-26-2023 / \$0

Appraiser

BRITTANY MCINTYRE

Property Class RMV Class

100 100 MA 09

SA

NH WF 903

Site	Situs Address	City
1	35700 AIRPORT WAY	COUNTY

			Value Summary			
Code Ar	ea	RMV	MAV	AV	RMV Exception	CPR %
2202	Land	198,480		Land	0	
	Impr	0		Impr	0	
Code	Area Total	198,480	92,140	92,140	0	
G	rand Total	198,480	92,140	92,140	0	

						Land Breakdown			
Code Area	ID#	RFPD	Ex	Plan Zone	Value Source	Trend %	Size	Land Class	Trended RMV
2202	1	~		PCW-R2	Market	117	0.21 AC		168,480
					OSD - AVERAGE	100			30,000
1 1						Code Area Total	0.21 AC		198,480

			0.0 110		Improvement Breakdown			
Code		Year	Stat		Trend			
Area	ID#	Built	Class Des	cription	%	Total Sqft	Ex% MS Acct	Trended RMV

Exemptions / Special Assessments / Notations

Notations

- DESTROYED OR DAMAGED PROPERTY, JULY 1 ASMT DATE 308.146(6) ADDED 2024
- ACT OF GOD RMV & MAV ADJUSTED 308.146 ADDED 2024
- ACT OF GOD PRORATED 308.425 ADDED 2023


Comments

10/19/06 input inventory. gb 12/6/06 Added acreage. dv 01/29/14 Reappraised land; tabled values. RBB 7/8/24 July 1 Reassessment; Residence completely destroyed in fire in June. RMV and MAV adjusted. Taxes were prorated for the 2023-24 tax year. LM

Page 1 of 1 4/11/2025 2:50 PM




Printed on 2 / 26 / 2025



https://www.oregon.gov/dsi/WW/Pages/SWI.aspx

National Flood Hazard Layer FIRMette





Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

Without Base Flood Elevation (BFE)

Regulatory Floodway

0.2% Annual Chance Flood Hazard, Area depth less than one foot or with drainage of 1% annual chance flood with average areas of less than one square mile Zone Future Conditions 1% Annual

Area with Reduced Flood Risk due to Chance Flood Hazard Zone X Levee. See Notes. Zone X

Area with Flood Risk due to Levee Zone D

No screen Area of Minimal Flood Hazard Zone X

Effective LOMRs

Area of Undetermined Flood Hazard Zone

Channel, Culvert, or Storm Sewer STRUCTURES | 111111 Levee, Dike, or Floodwall GENERAL

17.5

Cross Sections with 1% Annual Chance Water Surface Elevation

Base Flood Elevation Line (BFE) Coastal Transect me filme

Coastal Transect Baseline **Jurisdiction Boundary**

Hydrographic Feature Profile Baseline

OTHER FEATURES

Digital Data Available

No Digital Data Available Unmapped

MAP PANELS

The pin displayed on the map is an approximate point selected by the user and does not represe an authoritative property location.

This map complies with FEMA's standards for the use of The basemap shown complies with FEMA's basemap digital flood maps if it is not void as described below.

authoritative NFHL web services provided by FEMA. This map reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or The flood hazard information is derived directly from the was exported on 2/26/2025 at 7:41 PM and does not become superseded by new data over time. This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.

EXHIBIT B



Land Use Application

Rev. 6/9/23

Tillamook County Department of Community Development 1510-B Third Street. Tillamook, OR 97141 | Tel: 503-842-3408 Fax: 503-842-1819

www.co.tillamook.or.us

OFFICE USE ONLY

PLANNING APPLICATION

Address: 34635 HIII S. City: Pacific City State:	erty Owner) 503-965-7009 + OR Zip: 97135 ome SCom Way () Zip: 97135	NOV 1 8 2024 BY: Country Apt
Request: New Home	/ BURN Replace	mt
	*	
Type II	Type III	Type IV
	☐ Detailed Hazard Report	☐ Ordinance Amendment
☐ Farm/Forest Review		☐ Large-Scale Zoning Map
☐ Conditional Use Review	☐ Conditional Use (As deemed	Amendment
☐ Variance	by Director)	
☐ Exception to Resource or Riparian Setback	Ordinance Amendment	Plan and/or Code Text
■ Nonconforming Review (Major or Minor)	■ Map Amendment	Amendment
Development Permit Review for Estuary	☐ Goal Exception	
Development Hoodway	☐ Nonconforming Review (As	
☐ Non-farm dwelling in Farm Zone	deemed by Director)	
☐ Foredune Grading Permit Review	☐ Variance (As deemed by	
□ Neskowin Coastal Hazards Area	Director)	· ·
Location: Site Address: 35700 Arpon	-t Way 971	35
Map Number:	* ************************************	
Township Range	Si	ection Tax Lot(s)
Clerk's Instrument #:		
Authorization		
This permit application does not assure permit a obtaining any other necessary federal, state, an	approval. The applicant and/or property local permits. The applicant verifie	erty owner shall be responsible for s that the information submitted is
complete, accurate, and consistent with other in	nformation submitted with this appli	ication.
× Mas Makemales		Date
Property Owner Signature (Required)		11/18/2-1
Applicant Signature		Date
Applean Signature		

Form Instructions

U.S. DEPARTMENT OF HOMELAND SECURITY Federal Emergency Management Agency National Flood Insurance Program

OMB Control No. 1660-0008 Expiration Date: 06/30/2026

ELEVATION CERTIFICATE

IMPORTANT: MUST FOLLOW THE INSTRUCTIONS ON INSTRUCTION PAGES 1-11
Copy all pages of this Elevation Certificate and all attachments for (1) community official, (2) insurance agent/company, and (3) building owner

SECTION A – PROPERTY INFORMATION	FOR INSURANCE COMPANY USE
A1. Building Owner's Name: McREYNOLDS, MALI	Policy Number:
A2. Building Street Address (including Apt., Unit, Suite, and/or Bldg. No.) or P.O. Route and Box No.: 35700 AIRPORT WAY	Company NAIC Number:
City: PACIFIC CITY State: OR	ZIP Code: 97135
A3. Property Description (e.g., Lot and Block Numbers or Legal Description) and/or Tax Parcel Nu BLOCK 2, LOT 5, RIVERGATE ~ 4S-10-30-BD, TAX LOT 6100, TILLAMOOK COUNTY, OREGON	mber:
A4. Building Use (e.g., Residential, Non-Residential, Addition, Accessory, etc.): RESIDENTIAL	L
A5. Latitude/Longitude: Lat. 45.19556 Long. 123.95917 Horiz. Datum:	NAD 1927 NAD 1983 ☐ WGS 84
A6. Attach at least two and when possible four clear color photographs (one for each side) of the b	puilding (see Form pages 7 and 8).
A7. Building Diagram Number: 7	,
A8. For a building with a crawlspace or enclosure(s):	
a) Square footage of crawlspace or enclosure(s): 1604 sq. ft.	
b) Is there at least one permanent flood opening on two different sides of each enclosed area?	Yes No NA
 c) Enter number of permanent flood openings in the crawlspace or enclosure(s) within 1.0 foot Non-engineered flood openings: N/A Engineered flood openings: 10 	above adjacent grade:
d) Total net open area of non-engineered flood openings in A8.c: N/A sq. in.	
e) Total rated area of engineered flood openings in A8.c (attach documentation – see Instruction	ons): 2000 sq. ft.
f) Sum of A8.d and A8.e rated area (if applicable see Instructions): 2000 sq. ft.	44407-15100-15100-1510-1510-1510-1510-1510-
A9. For a building with an attached garage:	
a) Square footage of attached garage: N/A sq. ft.	
b) Is there at least one permanent flood opening on two different sides of the attached garage?	Yes No No NA
c) Enter number of permanent flood openings in the attached garage within 1.0 foot above adjated Non-engineered flood openings: N/A Engineered flood openings: N/A	acent grade:
d) Total net open area of non-engineered flood openings in A9.c: N/A sq. in.	
e) Total rated area of engineered flood openings in A9.c (attach documentation – see Instructio	ns): N/A sq. ft.
f) Sum of A9.d and A9.e rated area (if applicable – see Instructions):N/A sq. ft.	
SECTION B - FLOOD INSURANCE RATE MAP (FIRM) INFOR	RMATION
B1.a. NFIP Community Name: TILLAMOOK COUNTY B1.b. NFIP Com	munity Identification Number; 410196
B2. County Name: TILLAMOOK B3. State: OR B4. Map/Panel No.:	
B6. FIRM Index Date: 09/28/2018 B7. FIRM Panel Effective/Revised Date: 09/28/201	
B8. Flood Zone(s): AE B9. Base Flood Elevation(s) (BFE) (Zone AO, use E	***************************************
B10. Indicate the source of the BFE data or Base Flood Depth entered in Item B9: X FIS FIRM Community Determined Other:	
B11. Indicate elevation datum used for BFE in Item B9: NGVD 1929 K NAVD 1988 Other	/Source:
B12. Is the building located in a Coastal Barrier Resources System (CBRS) area or Otherwise Prote Designation Date: CBRS OPA	
313. Is the building located seaward of the Limit of Moderate Wave Action (LiMWA)? Yes	No

Form Instructions

ELEVATION CERTIFICATE

IMPORTANT: MUST FOLLOW THE INSTRUCTIONS ON INSTRUCTION PAGES 1-11

Building Street Address (including Apt., Unit, Suite	e, and/or Bldg. No.) o	r P.O. Route and Box	: No.:	FOR INS	URAN	ICE (COMPANY USE
35700 AIRPORT WAY	- OP	Omion	F	Policy Nu	mber:		
City: PACIFIC CITY	State: OR	ZIP Code: 97135		Company	NAIC	Num	ber:
SECTION C - BUIL	DING ELEVATIO	N INFORMATION	(SURVEY R	QUIRE	D)		
C1. Building elevations are based on: Con *A new Elevation Certificate will be required C2. Elevations – Zones A1–A30, AE, AH, AO,	when construction	of the building is com	plete.				
C2. Elevations – Zones A1–A30, AE, AH, AO, A A99. Complete Items C2.a–h below accord Benchmark Utilized: TILL.CO.SURVEY PC	ing to the Building D	i–v30, v (with BFE), hagram specified in It Vertical Datum:	AR, AR/A, AF tem A7. In Pue NAVD 1988	VAE, AR erto Rico	iA1–A: only, e	30, Ai ∍nter	R/AH, AR/AO, meters.
Indicate elevation datum used for the elevations NGVD 1929 NAVD 1988 Other		h) below.					Windows .
Datum used for building elevations must be the source of the conversion factors.	same as that used for	or the BFE. Conversion	on factor used	-	Yes	Ď	
 a) Top of bottom floor (including basement, 	, crawlspace, or enc	losure floor):	14.3	,,,,,,,,,		e me	asurement used meters
b) Top of the next higher floor (see Instruction	ions):		23,5	31 🛛	feet		meters
 c) Bottom of the lowest horizontal structural 	I member (see Instru	ictions):	N/A	<u> </u>	feet	П	meters
d) Attached garage (top of slab):			N/A	<u> </u>	feet		meters
 e) Lowest elevation of Machinery and Equip (describe type of M&E and location in Se 	oment (M&E) servici ction D Comments a	ng the building area):	19.	1 🛐	feet	П	meters
f) Lowest Adjacent Grade (LAG) next to bu	rilding: X Natural	Finished	13.	7 X	feet	П	meters
g) Highest Adjacent Grade (HAG) next to be	uilding: X Natural	Finished	14.		feet	П	meters
 h) Finished LAG at lowest elevation of attac support: 	ched deck or stairs, i	ncluding structural	14	.3 🛛	feet		meters
SECTION D - SUR	VEYOR, ENGINE	ER, OR ARCHITE	CT CERTIFIC	CATION	Local Sale		
This certification is to be signed and sealed by a information. I certify that the information on this called statement may be punishable by fine or important.	land surveyor, engi	neer, or architect auti	horized by sta	e law to	cortifu	eleva nders	ation stand that any
Were latitude and longitude in Section A provide							
X Check here if attachments and describe in the							
Certifier's Name:DOUGLAS H. KELLOW	Licens	e Number: OR PLS 2	2027	T	housest the the same and a same a		1
Title: PROFESSIONAL LAND SURVEYOR	***************************************				REG	ISTE	RED
Company Name: KELLOW LAND SURVEYIN	G		***************************************		PROF	ESSI	IONAL
Address: P.O. BOX 335				1		(0	VEYOR
City: PACIFIC CITY	State: OF	ZIP Code: 97	135	L'eq.	/		Keller
Telephone: 503-801-3537	Email:dkellov	w@aol.com	***		Febr	REGO	3, 1983
0 1 7/ 11 00				-		202	
Signature: Dougles II Kelle		Date: 12/22/2					6/30/25
Copy all pages of this Elevation Certificate and all a							
Comments (including source of conversion factor A8e.) THE FLOOD VENTS ARE ENGINEERED "SI EACH VENT. 10X200=2000 SQ FT OR SQ IN-See AC2e.) ALL PROPOSED MACHINERY & EQUIPME NAVD 1988 ELEVATION TO COMPLY WITH THI	Attached ICC-ES REP	ORT FOR "SMARTV	ENTS".	FEETO	F FLO	OR SE	PACE PER



Most Widely Accepted and Trusted

ICC-ES Evaluation Report

ICC-ES | (800) 423-6587 | (562) 699-0543 | www.icc-es.org

Revised 06/2024 This report is subject to renewal 02/2025.

DIVISION: 08 00 00—OPENINGS

SECTION: 08 95 43—VENTS/FOUNDATION FLOOD VENTS



REPORT HOLDER:

SMART VENT PRODUCTS, INC.

EVALUATION SUBJECT:

SMART VENT® AUTOMATIC FOUNDATION FLOOD VENTS: MODELS #1540-520; #1540-521; #1540-510; #1540-511; #1540-570; #1540-574; #1540-524; #1540-514 FLOOD VENT SEALING KIT #1540-526



"2014 Recipient of Prestigious Western States Seismic Policy Council (WSSPC) Award in Excellence"




ICC-ES Evaluation Reports are not to be construed as representing aesthetics or any other attributes not specifically addressed, nor are they to be construed as an endorsement of the subject of the report or a recommendation for its use. There is no warranty by ICC Evaluation Service, LLC, express or implied, as to any finding or other matter in this report, or as to any product covered by the report.









www.icc-es.org | (800) 423-6587 | (562) 699-0543

A Subsidiary of the International Code Council®

ICC-ES Evaluation Report

Reissued February 2023

Revised June 2024

This report is subject to renewal February 2025.

ESR-2074

DIVISION: 08 00 00—OPENINGS Section: 08 95 43-Vents/Foundation Flood Vents

REPORT HOLDER:

SMART VENT PRODUCTS, INC.

EVALUATION SUBJECT:

SMART VENT® AUTOMATIC FOUNDATION FLOOD VENTS: MODELS #1540-520; #1540-521; #1540-510; #1540-511; #1540-570; #1540-574; #1540-524; #1540-514 FLOOD VENT SEALING KIT #1540-526

1.0 EVALUATION SCOPE

Compliance with the following codes:

- 2024, 2021, 2018, 2015, 2012, 2009 and 2006 International Building Code® (IBC)
- 2024, 2021, 2018, 2015, 2012, 2009 and 2006 International Residential Code® (IRC)
- 2024, 2021 and 2018 International Energy Conservation Code® (IECC)
- 2013 Abu Dhabi International Building Code (ADIBC)†

[†]The ADIBC is based on the 2009 IBC. 2009 IBC code sections referenced in this report are the same sections in the ADIBC.

Properties evaluated:

- Physical operation
- Water flow

2.0 USES

The Smart Vent® units are engineered mechanically operated flood vents (FVs) employed to equalize hydrostatic pressure on walls of enclosures subject to rising or falling flood waters. Certain models also allow natural ventilation.

3.0 DESCRIPTION

3.1 General:

When subjected to rising water, the Smart Vent® FVs internal floats are activated, then pivot open to allow flow in either direction to equalize water level and hydrostatic pressure from one side of the foundation to the other. The FV pivoting door is normally held in the closed position by a buoyant release device. When subjected to rising water, the buoyant release device causes the unit to unlatch, allowing the door to rotate out of the way and allow flow. The water

level stabilizes, equalizing the lateral forces. Each unit is fabricated from stainless steel. Smart Vent® Automatic Foundation Flood Vents are available in various models and sizes as described in Table 1. The SmartVENT® Stacking Model #1540-511 and FloodVENT® Stacking Model #1540-521 units each contain two vertically arranged openings per unit

3.2 Engineered Opening:

The FVs comply with the design principle noted in Section 2.7.2.2 and Section 2.7.3 of ASCE/SEI 24-14 [Section 2.6.2.2 of ASCE/SEI 24-05 (2012, 2009, 2006 IBC and IRC)] for a maximum rate of rise and fall of 5.0 feet per hour (0.423 mm/s). In order to comply with the engineered opening requirement of ASCE/SEI 24, Smart Vent FVs must be installed in accordance with Section 4.0.

3.3 Ventilation:

The SmartVENT® Model #1540-510 and SmartVENT® Overhead Door Model #1540-514 both have screen covers with 1/4-inch-by-1/4-inch (6.35 by 6.35 mm) openings, yielding 51 square inches (32 903 mm²) of net free area to supply natural ventilation. The SmartVENT® Stacking Model #1540-511 consists of two Model #1540-510 units in one assembly, and provides 102 square inches (65 806 mm²) of net free area to supply natural ventilation. Other FVs described in this report do not offer natural ventilation.

3.4 Flood Vent Sealing Kit:

The Flood Vent Sealing Kit Model #1540-526 is used with SmartVENT® Model #1540-520. It is a Homasote 440 Sound Barrier® (ESR-1374) insert with 21 - 2-inch-by-2-inch (51 mm x 51 mm) squares cut in it. See Figure 4.

4.0 DESIGN AND INSTALLATION

4.1 SmartVENT® and FloodVENT®:

SmartVENT® and FloodVENT® are designed to be installed into walls or overhead doors of existing or new construction from the exterior side. Installation of the vents must be in accordance with the manufacturer's instructions, the applicable code and this report. Installation clips allow mounting in masonry and concrete walls of any thickness. In order to comply with the engineered opening design principle noted in Section 2.7.2.2 and 2.7.3 of ASCE/SEI 24-14 [Section 2.6.2.2 of ASCE/SEI 24-05 (2012, 2009, 2006 IBC and IRC)], the Smart Vent® FVs must be installed as



- With a minimum of two openings on different sides of each enclosed area.
- With a minimum of one FV for every 200 square feet (18.6 m²) of enclosed area, except that the SmartVENT® Stacking Model #1540-511 and FloodVENT® Stacking Model #1540-521 must be installed with a minimum of one FV for every 400 square feet (37.2 m²) of enclosed area.
- Below the base flood elevation.
- With the bottom of the FV located a maximum of 12 inches (305.4 mm) above the higher of the final grade or floor and finished exterior grade immediately under each opening.

4.2 Flood Vent Sealing Kit

The Flood Vent Sealing Kit Model 1540-526 is used in conjunction with FloodVENT® Model #1540-520. When installed and tested in accordance with ASTM E283, the FV and Flood Vent Sealing Kit assembly have an air leakage rate of less than 0.2 cubic feet per minute per lineal foot (18.56 l/min per lineal meter) at a pressure differential of 1 pound per square foot (50 Pa) based on 12.58 lineal feet (3.8 lineal meters) contained by the Flood Vent Sealing Kit.

5.0 CONDITIONS OF USE

The Smart Vent® FVs described in this report comply with, or are suitable alternatives to what is specified in, those codes listed in Section 1.0 of this report, subject to the following conditions:

5.1 The Smart Vent® FVs must be installed in accordance with this report, the applicable code and the manufacturer's installation instructions. In the event of a conflict, the instructions in this report govern.

5.2 The Smart Vent® FVs must not be used in the place of "breakaway walls" in coastal high hazard areas, but are permitted for use in conjunction with breakaway walls in other areas.

6.0 EVIDENCE SUBMITTED

- 6.1 Data in accordance with the ICC-ES Acceptance Criteria for Mechanically Operated Flood Vents (AC364), dated August 2015 (editorially revised February 2024).
- 6.2 Test report on air infiltration in accordance with ASTM E283.

7.0 IDENTIFICATION

- 7.1 The ICC-ES mark of conformity, electronic labeling, or the evaluation report number (ICC-ES ESR-2074) along with the name, registered trademark, or registered logo of the report holder must be included in the product label.
- 7.2 The Smart VENT® models and the Flood Vent Sealing Kit described in this report must be identified by a label bearing the manufacturer's name (Smartvent Products, Inc.), the model number, and the evaluation report number (ESR-2074).
- 7.3 The report holder's contact information is the following:

SMART VENT PRODUCTS, INC. 19 MANTUA ROAD MOUNT ROYAL, NEW JERSEY 08061 (877) 441-8368

www.smartvent.com info@smartvent.com

TABL	E 1_	_840	DEL	CIT	EC

MODEL NAME	MODEL NUMBER	MODEL SIZE (in.)	COVERAGE ¹ (ft ²)		
FloodVENT®	1540-520	15 ³ / ₄ " X 7 ³ / ₄ "	200		
SmartVENT®	1540-510	15 ³ / ₄ " X 7 ³ / ₄ "	200		
FloodVENT® Overhead Door	1540-524	15 ³ / ₄ " X 7 ³ / ₄ "	200		
SmartVENT® Overhead Door	1540-514	15 ³ / ₄ " X 7 ³ / ₄ "	200		
Wood Wall FloodVENT®	1540-570	14" X 8 ³ / ₄ "	200		
Wood Wall FloodVENT® Overhead Door	1540-574	14" X 8 ³ / ₄ "	200		
SmartVENT® Stacker	1540-511	16" X 16"	400		
FloodVent® Stacker	1540-521	16" X 16"	400		

For SI: 1 inch = 25.4 mm; 1 square foot = m2

¹The coverage area in square feet for each model is equivalent to the performance of the same number of square inches of non-engineered openings.




FIGURE 1—SMART VENT: MODEL 1540-510




FIGURE 2—SMART VENT MODEL 1540-520




FIGURE 3—SMART VENT: SHOWN WITH FLOOD DOOR PIVOTED OPEN




FIGURE 4—FLOOD VENT SEALING KIT



ICC-ES Evaluation Report

ESR-2074 CBC and CRC Supplement

Reissued February 2023 Revised June 2024

This report is subject to renewal February 2025.

www.icc-es.org | (800) 423-6587 | (562) 699-0543

A Subsidiary of the International Code Council®

DIVISION: 08 00 00—OPENINGS

Section: 08 95 43—Vents/Foundation Flood Vents

REPORT HOLDER:

SMART VENT PRODUCTS, INC.

EVALUATION SUBJECT:

SMART VENT® AUTOMATIC FOUNDATION FLOOD VENTS: MODELS #1540-520; #1540-521; #1540-510; #1540-511; #1540-570; #1540-524; #1540-514 FLOOD VENT SEALING KIT #1540-526

1.0 REPORT PURPOSE AND SCOPE

Purpose:

The purpose of this evaluation report supplement is to indicate that Smart Vent® Automatic Foundation Flood Vents, described in ICC-ES evaluation report ESR-2074, have also been evaluated for compliance with codes noted below.

Applicable code editions:

■ 2022 California Building Code (CBC)

For evaluation of applicable chapters adopted by the California Office of Statewide Health Planning and Development (OSHPD) AKA: California Department of Health Care Access and Information (HCAI) and the Division of State Architect (DSA), see Sections 2.1.1 and 2.1.2 below.

■ 2022 California Residential Code (CRC)

2.0 CONCLUSIONS

2.1 CBC:

The Smart Vent® Automatic Foundation Flood Vents, described in Sections 2.0 through 7.0 of the evaluation report ESR-2074, comply with CBC Chapter 12, provided the design and installation are in accordance with the 2021 *International Building Code*® (IBC) provisions noted in the evaluation report and the additional requirements of CBC Chapters 12 and 16, as applicable.

2.1.1 OSHPD:

The applicable OSHPD Sections and Chapters of the CBC are beyond the scope of this supplement.

2.1.2 DSA:

The applicable DSA Sections and Chapters of the CBC are beyond the scope of this supplement.

2.2 CRC:

The Smart Vent® Automatic Foundation Flood Vents, described in Sections 2.0 through 7.0 of the evaluation report ESR-2074, comply with the CRC, provided the design and installation are in accordance with the 2021 *International Residential Code*® (IRC) provisions noted in the evaluation report.

This supplement expires concurrently with the evaluation report, reissued February 2023 and revised June 2024.





ICC-ES Evaluation Report

ESR-2074 FBC Supplement

Reissued February 2023 Revised June 2024 This report is subject to renewal February 2025.

www.icc-es.org | (800) 423-6587 | (562) 699-0543

A Subsidiary of the International Code Council®

DIVISION: 08 00 00—OPENINGS

Section: 08 95 43—Vents/Foundation Flood Vents

REPORT HOLDER:

SMART VENT PRODUCTS, INC.

EVALUATION SUBJECT:

SMART VENT® AUTOMATIC FOUNDATION FLOOD VENTS: MODELS #1540-520; #1540-521; #1540-510; #1540-511; #1540-570; #1540-574; #1540-524; #1540-514 FLOOD VENT SEALING KIT #1540-526

1.0 REPORT PURPOSE AND SCOPE

Purpose:

The purpose of this evaluation report supplement is to indicate that Smart Vent® Automatic Foundation Flood Vents, described in ICC-ES evaluation report ESR-2074, have also been evaluated for compliance with the codes noted below.

Applicable code editions:

- 2023 Florida Building Code—Building
- 2023 Florida Building Code—Residential

2.0 CONCLUSIONS

The Smart Vent® Automatic Foundation Flood Vents, described in Sections 2.0 through 7.0 of the evaluation report ESR-2074, comply with the Florida Building Code—Building and the Florida Building Code—Residential, provided the design requirements must be determined in accordance with the Florida Building Code—Building or the Florida Building Code—Residential, as applicable. The installation requirements noted in ICC-ES evaluation report ESR-2074 for 2021 International Building Code® meet the requirements of the Florida Building Code—Building or the Florida Building Code—Residential, as applicable.


Use of the Smart Vent® Automatic Foundation Flood Vents has also been found to be in compliance with the High-Velocity Hurricane Zone provisions of the Florida Building Code—Building and the Florida Building Code—Residential.

For products falling under Florida Rule 61G20-3, verification that the report holder's quality assurance program is audited by a quality assurance entity approved by the Florida Building Commission for the type of inspections being conducted is the responsibility of an approved validation entity (or the code official when the report holder does not possess an approval by the Commission).

This supplement expires concurrently with the evaluation report, reissued February 2023 and revised June 2024.



35700 AIRPORT WAY HYDRAULIC ANALYSIS REPORT



prepared for Ian Spath, Pacific City Homes

prepared by

Jake Hofeld, P.E.



November 4, 2024





Digitally signed by Jake Hofeld Date: 2024.11.07 17:08:32 -08'00'

EXPIRES: 6/30/2025



Contents

INTRODUCTIO	ON	2
HYDRAULIC N	NODELING METHODOLOGY	2
	Existing Conditions Model	2
	Proposed Conditions Model	3
	Boundary Conditions	3
	Peak Flow Hydrology	4
RESULTS	4	
CONCLUSION	S	4

List of Figures

Figure 1: Tax Lot Location Map

Figure 2: FEMA FIRM Panel

Figure 3: Property Survey and Site Plan

Figure 4: Proposed Plans and Elevations

Figure 5: Hydraulic Analysis Overview Map of Proposed Project

List of Attachments

Attachment A – HEC-RAS Model Output Files



INTRODUCTION

Waterways Consulting Inc. (Waterways) has been retained by Ian Spath from Pacific City Homes to evaluate the hydraulic effects on the Nestucca River during a 100-year base flood discharge from an existing residential structure to a proposed residential structure. The project is located on the east (left) bank floodplain of the Nestucca River at 35700 Airport Way in Pacific City, Or (Figure 1). The existing property currently does not contain any structures, as a previous residential building was destroyed in a fire. The proposed residential structure will replace the previous existing building and will include a 1575 square foot footprint house in approximately the same location within the property as the previous house. The new structure includes a covered entry on the street side of the house, and two covered overhanging balcony decks on the river side of the second story and the east side of the house. The entire property is located within the FEMA designated floodway, effective September 28, 2018 (Figure 2).

The following report has been prepared to support floodplain development permitting with Tillamook County for the proposed project and presents our hydraulic analysis of existing and proposed conditions for the 100-year flood event along the Nestucca River within the vicinity of the proposed residential structure. This report is based on the guidance outlined in Section 3.510(9)(a) of the Tillamook County Land Use Ordinance which requires, "...certification is provided by a professional registered civil engineer demonstrating through hydrologic and hydraulic analysis performed in accordance with standard engineering practice that such encroachment shall not result in any increase in flood levels during the occurrence of the based flood discharge."

HYDRAULIC MODELING METHODOLOGY

The Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) has mapped Nestucca River at the project area as a Special Flood Hazard Area (SFHA) within the regulatory floodway Zone AE (Figure 2). Tillamook County provided Waterways with a hydraulic model of the Nestucca River covering the project area for a Letter of Map Revision (LOMR), effective September 24, 2015 (Case. Number 14-10-1727P). The LOMR and corresponding hydraulic model conducted in the United States Army Corps of Engineers (USACE) Hydraulic Engineering Center River Analysis Software (HEC-RAS) by West Consultants updated the previous modeling and FIRM Panels dated August 1, 1978. All elevations are referenced to a NAVD 88 vertical datum. This model was used as the basis for all hydraulic modeling.

Waterways updated the hydraulic analysis using HEC-RAS, version 6.4.1. A one-dimensional hydraulic model was completed to characterize the existing and proposed conditions at the project site during the 100-year recurrence interval peak flow at the Nestucca River. Five additional cross sections were added to the provided model in the vicinity of the project area (property). The two modeling scenarios include the Existing Conditions Model ("Ex. Cond." is the plan identifier in the model) and the Proposed Conditions Model ("Prop. Cond." is the plan identifier in the model). **Figure 5** shows the proposed project location, cross section locations used in the hydraulic analysis, and the effective FEMA floodplain and floodway boundaries (FEMA 2018).



Existing Conditions Model

Additional cross sections added to the LOMR model were sampled from a terrain surface derived from LiDAR data from the Department of Geology and Mineral Industries (DOGAMI) North Coast collected by Watershed Sciences Inc. in 2009. Bathymetry for the additional cross sections were interpolated from upstream and downstream cross sections of the LOMR model. The existing house was modeled as a blocked obstruction in the existing conditions model. **Figure 3** shows the property survey with both the existing and proposed house locations.

The downstream model boundary extends approximately 0.85 miles downstream of the project area and the upstream model boundary extends approximately 3.0 miles upstream of the project area (**Figure 5**). The bridge crossing geometry at Ferry Street and at Pacific Avenue upstream of the project area were included in the model from drawings provided by Oregon Department of Transportation (ODOT) and Tillamook County. Hydraulic roughness values for the additional cross sections were based on values published in the provided model. Hydraulic roughness values, known as Manning's Roughness, for the additional cross sections are outlined in **Table 1**.

Table 1. Manning's Roughness for Different Land Use Types

Land Use Type	Manning's 'n'
Channel	0.031
Open Pervious Areas (grassed)	0.04
Residential Area	0.08
Open Pervious Areas (trees)	0.10

Proposed Conditions Model

The proposed conditions model included the additional cross sections created in the existing conditions model. The existing condition terrain was updated with the proposed residential structure footprint provided by design drawings supplied by the client (**Figure 4**). The proposed residential structure was modeled as a blocked obstruction at cross sections located at the upstream and downstream sides of the proposed structure. The blocked obstruction is limited to the footprint of the structure at ground level. The posts associated with the second story overhanging decks are omitted from the model as these are considered negligible features in terms of ability to obstruct water during a flood event. The proposed conditions model did not update the existing topography of the site surrounding the proposed structure.

Boundary Conditions

The downstream boundary condition used in the two models was set to a known water surface elevation of 14.15 feet (NAVD 88) per the provided model. The downstream boundary condition is located downstream of FEMA Cross Section A near where Nestucca River meets the Nestucca Bay.



Peak Flow Hydrology

According to the FEMA FIS report and the provided model, the 100-year peak flow event for this portion of the Nestucca River is 49,700 cubic feet per second (cfs). Therefore, 49,700 cfs was assumed for the 100-year peak flow (i.e. base flood discharge) in all models.

RESULTS

Results of the hydraulic modeling are presented in **Attachment A**. These results show that the proposed structure will not result in a rise to the water surface elevations at any cross sections in the model. No change between the Existing Conditions Model and Proposed Conditions Model can likely be attributed to the relatively small change in building footprints as compared to a much larger, wider floodplain area.

CONCLUSIONS

The results of this hydraulic analysis indicate no rise in the 100-year water surface elevations for the Proposed Conditions Model when compared to the Existing Conditions Model. Based on this, the proposed project satisfies the requirement of Section 3.510(9)(a) of the Tillamook County Land Use Ordinance.




REFERENCES


- Federal Emergency Management Agency. 2018. Flood Insurance Rate Maps (FIRMs) for Tillamook County (panel 0855), Oregon and Incorporated Areas. September 28, 2018.
- Federal Emergency Management Agency. 2018. Flood Insurance Study (FIS) for Tillamook County, Oregon and Incorporated Areas. September 8, 2018.
- U.S. Army Corps of Engineers. Hydrologic Engineering Center. Computer Program HEC-RAS Version 6.4.1 Davis, California. June 2023.
- U.S. Army Corps of Engineers. Hydrologic Engineering Center. Hydraulic Reference Manual. Version 5.0 Davis, California. February 2016.
- Watershed Sciences. LiDAR Remote Sensing Data Collection Oregon North Coast. Prepared for Department of Geology and Mineral Industries (DOGAMI). December 21, 2009.
- West Consultants. Hydraulic Engineering Center River Analysis Software (HEC-RAS) Model of the Nestucca River. 2014.




Figures

35700 Airport Way 6










FIGURE 4: Proposed Plans and Elevations

GENERAL NOTES

FOR THE SECRET OF THE CASE OF ALTHOUGH IN MALE.

BULL SOURCE OF THE CASE OF THE CASE OF THE SECRET OF THE CASE OF THE CASE OF THE SECRET OF THE CASE OF THE SECRET OF THE CASE OF TH 5. WHEN GYPSUM WALL BOARD IS USED AS A BASE FOR TILE IN TUB AND SHOWER AND WATER OLOGIST AREAS WATER-RESISTANT GYPSUM BROKBOARD COMPLYING WITH F702.4.2. 4 TOLE STOKERS
FOR THE STOKERS A ALTIC MULTUROUS RESPENDENCE IN SOFT THE ATTO PREADS NET AREA FOR HALT THE WARE STORTED THE ATTO PREADS NET AREA FOR HALT THE WEST STORTED THE ATTO PRODUCE THE ATTO PRODUCE SHEATH OF A SPACE SETWED NOTATION AND POOT SHEATH OF A SPACE SETWED NOTATION AND POOT SHEATH OF A SPACE STORTE RESTS ABOVE INSULATION. SO INVENTIONS TO SERVE THE SOURCE THAN 44" FROM INVESTIGATION SUL THE SERVEN MICRORISM SERVEN CAREL SHALL NOT FELLOWER THAN 44" FROM INVIGATION SUL AND SHALL HAVE WEET ALL DASS DOES SHALL BE SHET IN CARED WITH AMMAND TO THE CONSTRUCTION WITH MANCH LOUIS SLOWIG GLUSS DOODS SHALL BE SHET IN CARED WITH AMMAND ON TRAININED CALLS. ALL FACTORY: BULT WINDOWS AND DOODS SHALL COMPLY WITH THE FOLLOWING CRITERIA FOR MAXIMUM ALLOWABLE AIR INFLITRATION RATES. WALLS R-21 BOOF R30C @ VAULTED CELINGS : R49 @ FLAT CELINGS UNDEFFLOOR R38 PROTECTION OF THE PROPERTY OF VENTILATION INSULATION

ns on this drawing shall take preced is. Verify all dimensions, conditions, etc work before proceeding

16. ALLWOOD, NOLUDING POSTS, WITHIN & OF GROUND SHALL BE PRESSURE TREATED.
17. AWEATHER-RESSTANT PIGD BAFFLE, EXTRIDING ABOVE THE INSULATION AT EAVE OR SOFFIT VEHTS IS PRED.

7 ALL EXIT DOORS WITH A NICHT LATCH. DEAD BOLT OR SECURITY CHAN SHALL BE OPBLABLE FROM THE MISIDE WITHOUT THE USE OF AKEY OR TOO. AND MOUNTED AT A HEIGHT NOT EXCEEDING 48" ABOVE THE FNISH FLOOR

THESE RATES MUST BE SUBSTANTIATED BY TESTING TO STANDARD ASTM. E 283-73

FOUNDATION BOLTS SHALL BE NOT LESS THAN 12" DIAMETER STEEL BOLTS EMEDDED AT LEAST 7 INTO CONDREST BY ACKED 72 ON CENTER MAXIMAN, WITH AT LEAST TWO BOLTS PER PLATE OF SILL AND 1 BOLT WITHIN 72 OF BIOS AND CAPIETS. BAD 19 UNLESS NOTED OTHERWISE.

15 COLUMNS AND POSTS SHALL BE ADEOUATELY ANCHORED TO PREVENT LATERAL DISPLACEMENT PA073

The Design Department, Inc.
Creating Your Perfect Space
1523 Bocs Ratan by
Lake Oswego, Oregon 97034
(503) 332 - 3796

ILLUMINATE BOTH INTERIOR AND EXTERIOR STARWAYS INCLUDING LANDINGS AND THEADS. F333.6 AND R333.7

8 A NON - REMOVABLE BACKFLOW PREVENTION DEVICE IS REQUIRED ON ALL EXTERIOR HOSE BIBBS. OPSC

9 A 36 MINMUM LANDING IS REQUIRED AT ALL EXTERIOR DOCHS. R311.3 THE LANDING SHALL NOT BE MORE THAN 8.14" BELOW THE TOP OF THE THRESHOLD.

PRODOS SARANNS PERROIT 7, APRLES TO NITBROR AND EXTEROR STARS)

A STANDAN BOS AND SANAMANIA FINIS PEODIED DE PRODOE A 15 - 2 SF DAMETER

A SANAMANIA SI PRODUEDA TERBIT STARTO 3 ORANDER BESES PROVIDE A 15 - 2 SF DAMETER

B YALL MITTAL SIN B PETFERNAMANIA AND BONAMA AND BONDETTED & 4-27 SF A SECRET FELD ORGANIC

C HARDALIS MICHAEL ALSO TRUCTON AS CANAFORIS SHALL BEST SF A FOCK T FELD ORGANIC

PRODUEDA SANAMANIA SAD TRUCTON AS CANAFORIS SHALL BEST SF A FOCK T FELD ORGANIC

PRODUEDA SANAMANIA SAD TRUCTON AS CANAFORIS SHALL BEST SF A FOCK T FELD ORGANIC

PRODUEDA SANAMANIA SAD TRUCTON AS CANAFORIS SHALL BEST SF A FOCK T FELD ORGANIC

PRODUEDA SANAMANIA SAD TRUCTON AS CANAFORIS SHALL BEST SF A FOCK T FELD ORGANIC

PRODUEDA SANAMANIA SAD TRUCTON AS CANAFORIS SHALL BEST SF A FOCK T FELD ORGANIC

PRODUEDA SANAMANIA SANAMANIA SAD TRUCTON AS CANAFORIS SHALL BEST ST ST SANAMANIA SANAMA

THE GRADE AROUND FOUNDATION WALLS SHALL FALL AMINMUM OF 6" IN THE FIRST 10 FEET

MN. CLEARANCE OF SILL TO FINISHED GRADE 6" PA041.6.

5 5 4

ATTENTION FRAMERI CRITICALI SEE "S" SHEETS FOR STRUCTURAL INFORMATION

Custom Home Plan for: Mali McReynolds Pacific City, Oregon

General Notes

PAPOUG CEC POSTICE DIG RER ESTIDAL CODE
A FOR CUTETS HEAVEDUS.
B AT NOT ESTS HEAVEDUS.
B AT NOT ESTS HEAVEDUS.
B AT NOT ESTS HEAVED SAPE COUNTY ROBED BEASEWINT
B AT NOT ESTS HEAVED SAPE COUNTY ROBED BEASEWINT
B AT NOT ESTS HEAVED SAPE COUNTY ROBED BEASEWINT
B AT NOT ESTS HEAVED SAPE COUNTY ROBED BEASEWINT
B AT NOT ESTS HEAVED SAPE TO THE PASSOO AT TH PROVIDE AT LEAST TWO SEPERATE 20 AMP CIRCUITS TO KITCHEN APPLIANCES. AND AT LEAST ONE SEPERATE 20 AMP CIRCUIT TO LAUNDRY APPLIANCES.

PROVICE RECIPICACION SE REQUERED Y VEGEO CON RA 800 00 A OUTLES ARE REGO AT PROTOCIO MAY SPACED COMPANIE RETENDE B OUTLES ARE REGO MAN MAY SPACE SOM WORTH THAN 12 AT FREE TO B OUTLES ARE REGO AT REGO AT A REGO AT SPACE SOM SPACE AND A PROTOCIO DE PROTOCIO PARTICIPATOR DE PROTOCIO D

A GROUNDING ELECTRODE, AT ELECTROAL SERVICE IS REQUIRED.

NOSISSING OF PRODUMENTED DIA AT THE PROPRIED TO A REMAIN BY CONTINGE THE PROPRIED BY A REMAIN BY THE PROPRIED BY A REMAIN BY THE PROPRIED BY ALL EXTEND 12" MINMUM ABOVE THE PLATE LINE

ELECTRICAL NOTES

5. LIGHT FIXTURES IN TUB OR SHOWER ENCLOSURES SHALL BE LABLE * SUITABLE FOR DAMP LOCATIONS*

© ECMED SHORE DETECTORS OB DETECTORS ALL DETECTORS SHALL BE NUTFICIALLED AND SHALL BE NUTFICIALLED WHICH WILL BE NUTFICIAL OF THE ALAWARS IN THE HOUSE AND SHE IN ALL THE ALL OF THE ALAWARS IN THE HOUSE AND SHE IN ALL THE SEEPHOL AND ALAWARS TO THE NUTFICIAL DETECTORS AND ALL THANK A BATTERS BOOKUP THE S = EXHAUST FAN
ALL ERHUSTDUCTS SHALL BE FIGD MET AL
AND SHALL BE FITTED WITH A TIGHT FITTING
BACKGRAFT DAMPRE CPARBE OF CLOSING
WHEN THE FAN IS NOT IN USE

INDEX OF DRAWINGS

NDEX OF DRAWINGS, GENERAL NOTES, FOUNDATION NOTES EXISTING CONDITIONS TOPOGRAPHICAL SURVEY, PROPICED SITE PLAN EXTERIOR ELEVATIONS GARGE FLOOR PLAN FRAMING SECTIONS FOUNDATION PLAN MAIN FLOOR PLAN ROOF PLAN

GOVERNING CODE

2021 OREGON RESIDENTIAL SPECIALTY CODE

6 ALL SWITCHES OUTLETS AND ENVIRONMENTAL CONTROLS
SPALL BE MOUNTED NOT LESS THAN 15' NOR MORE THAN
VERTICALLY
VERTICALLY

ALL EXHAUST DUCTS SHALL BE RIGID METAL, AND SHALL BE FITTED WITH A TIGHT FITTING BACKDRAFT DAMPER CAPABLE OF CLOSING WHEN THE FAN IS NOT IN USE DUCTS IN UNHEATED SPACES INCLUDING ATTICS SHALL BE INSULATED TO A MINIMUM OF P.4.

ENERGY CODE NOTES

FLOOR STRUCTURE, 34" T&G PLYWD DECKING GLUED & NAILED TOZX, F.J. @ 15 D.C. CPROSERICIONG @ MIDSPANS, SOLID BLANG @ BEARING EXTRAJUSIST UNDER PARALLEL WALLE.

ALL WOOD IN CONTACT W/ CONC TO BE PRESSURE THEATED OR PROTECTED WITH 56# FOLL, FOOFING

FOOTNIGS ARE TO BEAR ON UNDISTURBED SOIL. DEVIOLO CF ANY DECANIC MATERIAL AND STEPPED AS REQUIRED TO MANITAN THE PEO DEPTH BELOW THE FINAL GRADE.

FOUNDATION NOTES

6. PT. 2X6SIL PLATEST
7. FLOORSTRIPMING

PROVICE R-39 UNDERFLOOR INSULATION USE SPRING WIFES TO HOLD INSULATION TIGHT TO UNDERSIDE OF FLOOR SHEATHING SPACE WIPES PER INSTALLERS SPECS.

3 SOIL BEARING PRESSURE ASSUMED TO BE 1500 PSF ANY FILL UNDER GRADE SUPPORTED SLABS SAND

SEE PLAN DETAILS ON "S" SHEETS

FOUNDATION

SEE GENERAL NOTES

THROUGH S12 STRUCTURAL PLANS

ALL CONSTRUCTION SHALL CONFORM TO 2021 OFFICE DATO 1(1)

09.01.24 09.16.24 09.26.24 10.08.24


SHEET PROJECT NO 2524 PROGRESS DRAWINGS NOT FOR CONSTRUCTION


ORIGIN DATE 08.20.24

Custom Home Plan for: Mail McReynolds Pacific City, Oregon

one on this drawing shall take preceden ng. terify all dimensions, conditions, etc. work before proceeding. work before proceeding. To conditiod on any validations from the Or conditions shown on these drawings.

рвојест ^{ио} 2524






ATTENTION FRAMERI
CRITICALI
SEE "S" SHEETS FOR
STRUCTURAL
INFORMATION

The Design Department, Inc.
Creating Your Perfect Space
1523 Boca Ratan Dr.
Lake Cswego, Chegon 97034
(503) 332 - 3796

Without disnotation on this drawing shall like procedure over the control of the

Custom Home Plan for: Mail McReynolds Pacific City, Oregon

PROJECT NO ORIGIN DATE 08.20.24 PROGRESS DRAWINGS NOT FOR CONSTRUCTION






Attachment A
HEC-RAS Output Files


HEC-RAS River: Nestucca River Reach: Lower Profile: 100-YR


Reach Lower	22553.94 22553.94 22553.94 21008.6 21008.6 20157.05	100-YR 100-YR 100-YR	Ex. Cond. Prop. Cond.	Q Total (cfs) 49700.00 49700.00	Min Ch El (ft) -5.99	(ft) 20.47	(ft) 12.22	E.G. Elev (ft) 20.52	E.G. Slope (ft/ft) 0.000091	Vel Chni (fl/s) 3.07	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Lower Lower Lower Lower Lower Lower Lower Lower Lower	22553.94 21008.6 21008.6	100-YR 100-YR				20.47						***************************************	
Lower Lower Lower Lower Lower Lower Lower	21008.6 21008.6	100-YR	Prop. Cond.	49700.00				20.52	0.000001	0.01	32160.19	3643.05	0.11
Lower Lower Lower Lower Lower	21008.6				-5.99	20.47	12.22	20.52	0.000091	3.07	32160.36	3643.06	0.11
Lower Lower Lower Lower Lower	21008.6		Ex. Cond.	49700.00	-8.92	20.06		20.28	0.000261	F 20	17007 54	4740 50	0.00
Lower Lower Lower Lower		100-YR	Prop. Cond.	49700.00	-8.92	20.06		20.28	0.000261	5.20 5.20	17807.54 17807.65	1743.58 1743.58	0.20
Lower Lower Lower	20157.05												
Lower Lower	DOLET DE	100-YR	Ex. Cond.	49700.00	-9.15	19.91	12.36	20.07	0.000214	4.44	19949.16	2301.84	0.17
Lower	20157.05	100-YR	Prop. Cond.	49700.00	-9.15	19.91	12.36	20.07	0.000214	4.44	19949.27	2301.85	0.17
1000	19079.89	100-YR	Ex. Cond.	49700.00	-11.85	19.67		19.85	0.000231	5.04	20225.51	1888.65	0.18
Lower	19079.89	100-YR	Prop. Cond.	49700.00	-11.85	19.67		19.85	0.000231	5.04	20225.63	1888.66	0.18
Lower	40040.0	400.00		40700.00	7.00	40.50	44.05	10.01					
Lower	18019.8 18019.8	100-YR 100-YR	Ex. Cond. Prop. Cond.	49700.00 49700.00	-7.69 -7.69	19.50 19.50	11.35 11.35	19.64 19.64	0.000188	4.33	22110.72 22110.86	2667.83 2667.83	0.16
	(Ex 1=9)	e e e e e e e		10700.00	7.00	10.00	11.00	13.04	0.000100	4.55	22110.00	2007.03	0.10
Lower	17875.97	100-YR	Ex. Cond.	49700.00	-7.60	19.48	11.05	19.61	0.000170	4.14	22981.68	2676.65	0.16
Lower	17875.97	100-YR	Prop. Cond.	49700.00	-7.60	19.48	11.05	19.61	0.000170	4.14	22981.83	2676.65	0.16
Lower	17653.2	100-YR	Ex. Cond.	49700.00	-4.67	19.50	11.28	19.57	0.000096	3.23	29177.87	3181.44	0.12
Lower	17653.2	100-YR	Prop. Cond.	49700.00	-4.67	19.50	11.28	19.57	0.000096	3.23	29177.07	3181.44	0.12
	A CONTRACTOR	3 14 31 314											
Lower	15949.74	100-YR	Ex. Cond.	49700.00	-7.67	19.45	9.86	19.48	0.000032	1.91	46592.88	4377.52	0.07
Lower	15949.74	100-YR	Prop. Cond.	49700.00	-7.67	19.45	9.86	19.48	0.000032	1.91	46593.16	4377.52	0.07
Lower	14728.64	100-YR	Ex. Cond.	49700.00	-9.90	19.40	10.23	19.44	0.000044	2.47	37193.02	3855.12	0.09
Lower	14728.64	100-YR	Prop. Cond.	49700.00	-9.90	19.40	10.23	19.44	0.000044	2.47	37193.29	3855.12	0.09
Lower	14621.23			Bridge									
Lower	14544.91	100-YR	Ex. Cond.	49700.00	-8.62	19.38	10.32	19.42	0.000046	2.55	36776.38	3870.43	0.10
Lower	14544.91	100-YR	Prop. Cond.	49700.00	-8.62	19.38	10.32	19.42	0.000046	2.55	36776.66	3870.43	0.10
Lower	13541.26 13541.26	100-YR 100-YR	Ex. Cond. Prop. Cond.	49700.00 49700.00	-7.81 -7.81	19.33 19.33	10.21	19.38 19.38	0.000052 0.000052	2.51	32684.44 32684.66	3280.23	0.10
1.1	0 1 1 1 1 0 0	100 11	in the second	40700.00	-7.01	18.55	10,21	15.50	0.000032	2.51	32004.00	3280.23	0.10
Lower	12396	100-YR	Ex. Cond.	49700.00	-3.59	18.46		19.18	0.000466	7.08	9064.17	2047.98	0.30
Lower	12396	100-YR	Prop. Cond.	49700.00	-3.59	18.46		19.18	0.000466	7.08	9064.25	2047.98	0.30
Lower	11367.2	100-YR	Ex. Cond.	49700.00	-3.05	17.68	9.51	10.61	0.000027	7.00	7400.07	2007.74	2.05
Lower	11367.2	100-YR	Prop. Cond.	49700.00	-3.05	17.68	9.51	18.61 18.61	0.000627 0.000627	7.86 7.86	7498.27 7498.36	2007.74	0.35 0.35
	6. 00.00.000	1 7 1 1 1 1 1	SI E Crestado					, , , , ,	0.000021	7,00	7 100.00	2007.110	0.00
Lower	10048.77	100-YR	Ex. Cond.	49700.00	-3.49	16.91	9.18	17.76	0.000628	7.57	8607.56	2055.70	0.34
Lower	10048.77	100-YR	Prop. Cond.	49700.00	-3.49	16.91	9.18	17.76	0.000628	7.57	8607.73	2055.72	0.34
Lower	9942.323			Bridge									
	100 E 100 E												
Lower	9904.361	100-YR	Ex. Cond.	49700.00	-8.44	16.76	8.05	17.45	0.000550	6.97	9949.64	2093.46	0.31
Lower	9904.361	100-YR	Prop. Cond.	49700.00	-8.44	16.76	8.05	17.45	0.000550	6.97	9949.84	2093.46	0.31
Lower	8988.11	100-YR	Ex. Cond.	49700.00	-4.80	16.54	8.14	16.90	0.000336	5.39	12835.98	1977.94	0.24
Lower	8988.11	100-YR	Prop. Cond.	49700.00	-4.80	16.54	8.14	16.90	0.000336	5.39	12836.28	1977.97	0.24
Lower Lower	8192.259 8192.259	100-YR 100-YR	Ex. Cond. Prop. Cond.	49700.00 49700.00	-18.19 -18.19	16.28 16.28	6.30	16.65	0.000314	5.51	12794.84	2036.13	0.24
-OWG!	0102.230	100-110	Frop. Cond.	49700.00	-10.19	10.20	6,30	16.65	0.000314	5.51	12795.18	2036.14	0.24
Lower	7839.108	100-YR	Ex. Cond.	49700.00	-6.96	16.17	6.76	16.54	0.000316	5.20	12341.71	1874.39	0.24
Lower	7839.108	100-YR	Prop. Cond.	49700.00	-6.96	16.17	6.76	16.54	0.000316	5.20	12342.04	1874.41	0.24
Lower	6628.945	100-YR	Ex. Cond.	49700.00	-1.36	15.00	0.04	40.40	0.000040	204	11005.50	0.407.05	
Lower	6628.945	100-YR	Prop. Cond.	49700.00	-1.36	15.96 15.96	6.84	16.19 16.19	0.000213	3.94	14085.53 14085.87	3167.65 3167.67	0.19
			ug Komerney			,,,,,,	0.01	10.10	0.000210	0.01	14000.07	0107.07	0.13
Lower	6392.75	100-YR	Ex. Cond.	49700.00	-2.66	15.91	6.22	16.14	0.000198	3.95	14702.60	2923.31	0.18
Lower	6392.75	100-YR	Prop. Cond.	49700.00	-2.66	15.91	6.22	16.14	0.000198	3.95	14702.96	2923.32	0.18
Lower	6374.74	100-YR	Ex. Cond.	49700.00	-2.76	15.91	6.17	16.14	0.000199	3.96	14752.78	2944.51	0.10
ower	6374.74	100-YR	Prop. Cond.	49700.00	-2.76	15.91	6.17	16.14	0.000199	3.96	14670.74	2903.94	0.19
ower	6359.73 6359.73	100-YR	Ex. Cond.	49700.00	-2.84	15.90	6.14	16.14	0.000198	3.96	14860.28	2887.36	0.18
_ower	0309.73	100-YR	Prop. Cond.	49700.00	-2.84	15.90	6.14	16.14	0.000198	3.96	14750.31	2835.25	0.18
ower	6329.21	100-YR	Ex. Cond.	49700.00	-3.01	15.90	6.08	16.13	0.000195	3.94	15077.49	2820.66	0.18
ower	6329.21	100-YR	Prop. Cond.	49700.00	-3.01	15.90	6.08	16.13	0.000195	3.95	14952.97	2767.12	0.18
owe-	6200.60	100 VD	Ev. C	40700 00									
ower	6299.68 6299.68	100-YR 100-YR	Ex. Cond. Prop. Cond.	49700.00 49700.00	-3.17 -3.17	15.90 15.90	5.93 5.93	16.12 16.12	0.000188	3.89	15392.66 15392.66	2675.12	0.18
		1		10.00.00	3.17	10.00	5.93	10,12	0.000100	3.69	10092.00	2675.12	0.18
ower	4746.314	100-YR	Ex. Cond.	49700.00	-11.72	14.76	7.45	15.56	0.000672	7.30	7417.23	2442.34	0.34
ower	4746.314	100-YR	Prop. Cond.	49700.00	-11.72	14.76	7.45	15.56	0.000672	7.30	7417.23	2442.34	0.34
ower	3370.732	100-YR	Ex. Cond.	49700.00	-3.40	14.28	8.00	14.70	0.000100	5.50	0000 55	050:	
ower	3370.732	100-YR	Prop. Cond.	49700.00	-3.40	14.28	6.63	14.73 14.73	0.000430	5.53 5.53	9803.55 9803.55	3594.57 3594.57	0.27


HEC-RAS River: Nestucca River Reach: Lower Profile: 100-YR (Continued)


Reach	River Sta	Profile	Plan	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Crit W.S. (ft)	E.G. Elev (ft)	E.G. Slope (fl/ft)	Vel Chni (ft/s)	Flow Area (sq ft)	Top Width (ft)	Froude # Chl
Lower	2099.855	100-YR	Ex. Cond.	49700.00	-3.90	14.15	5.85	14.31	0.000175	3.42	17693.71	5262.50	0.17
Lower	2099.855	100-YR	Prop. Cond.	49700.00	-3.90	14.15	5.85	14.31	0.000175	3.42	17693.71	5262.50	0.17
















































































Nava Contracting & Engineering, Inc.

4106 S.E. Oak St,. Portland, Oregon 97214

Ph: (503) 238-0633; Email: navaengr4@gmail.com

Client: Mali McReynolds By: Matthew V. Nava P.E. Page:
Project: Lot 5 Block 2. Rivergate Subdivision Date: 11/05/2024

COVER SHEET

Description:

Structural Analysis and Design

Location:

Lot 5 Block 2

Rivergate Subdivision Pacific City, Oregon

Design Basis:

Code:

Oregon Structural Specialty Code 2022

Wind:

135 mph 3sec gust, Category II, Exposure D per ASCE 7 - 16

Seismic Zone: D2 Floor Live Load: 40 psf

Attic Live Load: 20 psf for Ht > 42", 10 psf for Ht < 42"

Deck Live Load": 60 psf

Snow:

25 psf

Roof Dead Load: 15 psf

Notes:

- 1. Timber connection hardware as indicated shall be from Simpson Strong Tie. Install hardware in accordance with Simpson installation requirements as provided in the most current manufacturers catalogs.
- 2. All Architectural considerations, including stairs and hand railings and their connections, interior and exterior finishes, fire ratings, egress requirements, flashing, insulation, setbacks, ventilation, height restrictions, etc are by others.
- 3. It is the owners and/or owners representative responsibility to coordinate with local building jurisdictions to determine if a Geological/Geotechnical investigation and/or report is required for the specific building location. The design as provided by myself is based on standard typical soil conditions and does not include any additional design requirements for special and/or unusual geological/Geotechnical considerations unless specifically noted.
- 4. All excavation, fill, compaction, and drainage by others.
- 5. Means and methods of construction including temporary shoring by others
- 6. Structural calculations herein are for analysis purposes only. DO NOT USE THE FLOOR PLANS, ELEVATIONS OR DIMENSIONS SHOWN HERE-IN FOR CONSTRUCTION. REFER TO DESIGN STRUCTURAL DRAWINGS FOR ALL CONSTRUCTION REQUIREMENTS.

Following Calculations and Design have been prepared by the undersigned:

Matthew V. Nava, P.E. Registration No. 13703

State: Oregon


Expiration Date: 12/31/2024

NAVA CONTRACTING & ENGINEERING, INC.

4106 SE Oak St, Portland, OR 97214 Ph: (503) 238-0633 navaengr4@gmail.com

Client: Mali McReynolds By: Matthew V. Nava, P.E. Page: .

Project: Lot 5 Block 2, Rivergate Subdivision Date: 11/05/2024



NAVA CONTRACTING & ENGINEERING, INC.

4106 SE Oak St, Portland, OR 97214 Ph: (503) 238-0633 navaengr4@gmail.com


Client: Mali McReynolds
Project: Lot 5 Block 2, Rivergate Subdivision

Date: 11/05/2024

1 20'-3"

2 18'-3"


3



NAVA CONTRACTING & ENGINEERING, INC.

4106 SE Oak St, Portland, OR 97214 Ph: (503) 238-0633 navaengr4@gmail.com

Client: Mali McReynolds By: Matthew V. Nava, P.E. Page: .



4106 SE Oak St, Portland, OR 97214

Ph: (503) 238-0633 navaengr4@gmail.com


Client: Mali McReynolds

By: Matthew V. Nava, P.E.

Page:

Project: Lot 5 Block 2, Rivergate Subdivision

Date: 11/05/2024




FOUNDATION PLAN SCALE: 1/8" = 1'-0"

4106 SE Oak St, Portland, OR 97214 Ph: (503) 238-0633 navaengr4@gmail.com

Client: Mali McReynolds By: Matthew V. Nava, P.E. Page:

Project: Lot 5 Block 2, Rivergate Subdivision Date: 11/05/2024




Wind Speed 135 mph (3 sec gust) Exposure D ω (wall) = 24.83 psf ω (eave) = -5.44 psf use ω (wall) = 9.6 psf (min) use ω (eave) = 4.8 psf (min)

4106 SE Oak St, Portland, OR 97214 Ph: (503) 238-0633 navaengr4@gmail.com

Client: Mali McReynolds By: Matthew V. Nava, P.E. Page: .

Project: Lot 5 Block 2, Rivergate Subdivision Date: 11/05/2024



Wind Speed 135 mph (3 sec gust) Exposure D ω (wall) = 24.83 psf ω (eave) = -5.44 psf use ω (wall) = 9.6 psf (min) use ω (eave) = 4.8 psf (min)

4106 SE Oak St, Portland, OR 97214 Ph: (503) 238-0633 navaengr4@gmail.com

Client: Mali McReynolds By: Matthew V. Nava, P.E. Page: .


Project: Lot 5 Block 2, Rivergate Subdivision Date: 11/05/2024




4106 SE Oak St, Portland, OR 97214 Ph: (503) 238-0633 navaengr4@gmail.com

Client: Mali McReynolds By: Matthew V. Nava, P.E. Page: .

Project: Lot 5 Block 2, Rivergate Subdivision Date: 11/05/2024 .



ROOF, RJ1 1 piece(s) 2 x 12 DF No.2 @ 19.2" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	471 @ 17' 4 1/4"	2578 (2.75")	Passed (18%)		1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	416 @ 3' 10 7/16"	2329	Passed (18%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1649 @ 10' 2 5/8"	3138	Passed (53%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.147 @ 10' 1"	0.754	Passed (L/999+)		1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.234 @ 10' 1 3/16"	1.005	Passed (L/772)		1.0 D + 1.0 S (Alt Spans)

Member Length : 18' 3 1/4" System : Roof

Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD Member Pitch : 3/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Beveled Plate - DF	5.50"	5.50"	1.50"	255	412	667	Blocking
2 - Beveled Plate - DF	2.75"	2.75"	1.50"	178	293	471	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 1" o/c	
Bottom Edge (Lu)	18' o/c	

[•]Maximum allowable bracing intervals based on applied load.

•Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 17' 6"	19.2"	15.0	25.0	Default Load


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumwent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



ROOF, RJ2 1 piece(s) 2 x 12 DF No.2 @ 19.2" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	235 @ 1 3/4"	2578 (2.75")	Passed (9%)		1.0 D + 1.0 S (All Spans)
	161 @ 1' 1 11/16"	2329	Passed (7%)	1.15	1.0 D + 1.0 S (All Spans)
Shear (lbs) Moment (Ft-lbs)	392 @ 3' 7 1/2"	3138	Passed (12%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.008 @ 3' 7 1/2"	0.359	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.013 @ 3' 7 1/2"	0.478	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length: 7' 8 1/2" System: Roof Member Type: Joist Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

Member Pitch: 3/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
- Beveled Plate - DF	2.75"	2.75"	1.50"	90	145	235	Blocking
2 - Beveled Plate - DF	2.75"	2.75"	1.50"	90	145	235	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	7' 6" o/c	
Bottom Edge (Lu)	7' 6" o/c	

- •Maximum allowable bracing intervals based on applied load.
- •Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

to 2" 45.0 Default Load	Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
	1 - Uniform (PSF)	0 to 7' 3"	19.2"	15.0	25.0	Default Load

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties weyernaeuser warrants that the sizing or its products will be in accordance with weyernaeuser product design criteria and published design values. Weyernaeuser expressly discialins any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC

ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

1 piece(s) 2 x 12 DF No.2 @ 24" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	657 @ 18' 10 1/4"	2578 (2.75")	Passed (25%)		1.0 D + 1.0 S (Alt Spans)
Shear (lbs)	586 @ 3' 10 3/16"	2329	Passed (25%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	2549 @ 10' 11 7/16"	3138	Passed (81%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.287 @ 10' 9 15/16"	0.850	Passed (L/712)		1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.461 @ 10' 10 1/8"	1.133	Passed (L/442)		1.0 D + 1.0 S (Alt Spans)

Member Length: 20' 4 1/16"

System : Roof Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD Member Pitch : 4/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Beveled Plate - DF	5.50"	5.50"	1.50"	349	551	900	Blocking
2 - Beveled Plate - DF	2.75"	2.75"	1.50"	252	405	657	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	4' 9" o/c	
Bottom Edge (Lu)	20' o/c	

[•]Maximum allowable bracing intervals based on applied load.

[•]Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 19'	24"	15.0	25.0	Default Load

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



ROOF, RJ4 1 piece(s) 2 x 12 DF No.2 @ 19.2" OC

Sloped Length: 16' 9"

10

16' 3"

Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	526 @ 1 3/4"	2578 (2.75")	Passed (20%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	452 @ 1' 1 11/16"	2329	Passed (19%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	2061 @ 8' 1 1/2"	3138	Passed (66%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.218 @ 8' 1 1/2"	0.822	Passed (L/906)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.352 @ 8' 1 1/2"	1.097	Passed (L/560)		1.0 D + 1.0 S (All Spans)

Member Length : 16' 11 13/16"

System: Roof Member Type: Joist Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 3/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Beveled Plate - DF	2.75"	2.75"	1.50"	201	325	526	Blocking
2 - Beveled Plate - DF	2.75"	2.75"	1.50"	201	325	526	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 7" o/c	
Bottom Edge (Lu)	16' 9" o/c	

- •Maximum allowable bracing intervals based on applied load.
- •Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 16' 3"	19.2"	15.0	25.0	Default Load


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser Englineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



ROOF, RJ5 1 piece(s) 2 x 12 DF No.2 @ 19.2" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	396 @ 2' 8 3/4"	5315 (5.50")	Passed (7%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	145 @ 3' 10 7/16"	2329	Passed (6%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	-241 @ 2' 8 3/4"	3138	Passed (8%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.004 @ 0	0.281	Passed (2L/999+)		1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.005 @ 0	0.375	Passed (2L/999+)		1.0 D + 1.0 S (Alt Spans)

Member Length: 8' 8 7/8" System: Roof Member Type: Joist Building Use: Residential Building Code: IBC 2018

Design Methodology : ASD Member Pitch : 3/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)			
	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Beveled Plate - DF	5.50"	5.50"	1.50"	151	244	396	Blocking
2 - Beveled Plate - DF	2.75"	2.75"	1.50"	53	99	152	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	8' 6" o/c	
Bottom Edge (Lu)	8' 6" o/c	

- •Maximum allowable bracing intervals based on applied load.
- •Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 8' 3"	19.2"	15.0	25.0	Default Load


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



ROOF, R1 1 piece(s) 5 1/2" x 13 1/2" 24F-V4 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	5649 @ 19' 7"	9453 (2.75")	Passed (60%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	4873 @ 1' 7"	15085	Passed (32%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	26949 @ 9' 11 1/2"	38037	Passed (71%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.530 @ 9' 11 1/2"	0.962	Passed (L/436)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.886 @ 9' 11 1/2"	1.283	Passed (L/261)		1.0 D + 1.0 S (All Spans)

Member Length : 19' 8 1/4"

System: Roof

Member Type: Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Critical positive moment adjusted by a volume/size factor of 0.99 that was calculated using length L = 19' 3".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- The specified glulam is assumed to have its strong laminations at the bottom of the beam. Install with proper side up as indicated by the manufacturer.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.69"	2327	3467	5794	Blocking
2 - Stud wall - DF	2.75"	2.75"	1.64"	2269	3380	5649	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	19' 8" o/c	
Bottom Edge (Lu)	19' 8" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 19' 8 1/4"	N/A	18.0		
1 - Uniform (PLF)	0 to 19' 8" (Front)	N/A	159.4	257.5	Linked from: RJ1, Support 1
2 - Uniform (PLF)	0 to 19' 8" (Front)	N/A	56.3	90.6	Linked from: RJ2, Support 2

Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC

ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

1 piece(s) 5 1/2" x 10 1/2" 24F-V4 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	4211 @ 1 1/4"	9453 (2.75")	Passed (45%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	3671 @ 1' 1 1/4"	11733	Passed (31%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	17680 @ 8' 7 1/4"	23244	Passed (76%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.577 @ 8' 7 1/4"	0.850	Passed (L/354)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.963 @ 8' 7 1/4"	1.133	Passed (L/212)		1.0 D + 1.0 S (All Spans)

Member Length: 17' 5 1/4"

System: Roof

Member Type: Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Critical positive moment adjusted by a volume/size factor of 1.00 that was calculated using length L = 17'.
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- The specified glulam is assumed to have its strong laminations at the bottom of the beam. Install with proper side up as indicated by the manufacturer.
- · Applicable calculations are based on NDS.

Supports		Bearing Length			to Suppor		
	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	2.75"	2.75"	1.50"	1689	2522	4211	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	1730	2583	4313	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	17' 5" o/c	
Bottom Edge (Lu)	17' 5" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 17' 5 1/4"	N/A	14.0		
1 - Uniform (PLF)	0 to 17' 5" (Front)	N/A	56.3	90.6	Linked from: RJ2, Support 2
2 - Uniform (PLF)	0 to 17' 5" (Front)	N/A	126.0	202.5	Linked from: RJ3, Support 2

Side loads are assumed to not induce cross-grain tension.


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 6 x 12 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2437 @ 10' 1"	9453 (2.75")	Passed (26%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	1863 @ 1' 5"	8244	Passed (23%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	5839 @ 5' 2 1/2"	10166	Passed (57%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.066 @ 5' 2 1/2"	0.488	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.110 @ 5' 2 1/2"	0.650	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length: 10' 2 1/4"

System: Roof

Member Type : Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

Supports	В	Bearing Length			to Suppor		
	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.50"	1033	1527	2559	Blocking
2 - Stud wall - DF	2.75"	2.75"	1.50"	983	1453	2437	Blocking

[•] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	10' 2" o/c	
Bottom Edge (Lu)	10' 2" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 10' 2 1/4"	N/A	16.0		
- Uniform (PLF) 0 to 10' 2" (Front)		N/A	56.3	90.6	Linked from: RJ2, Support 2
2 - Uniform (PLF)	- Uniform (PLF) 0 to 10' 2" (Front)		126.0	202.5	Linked from: RJ3, Support 2

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/ document-library.


ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



PASSED MEMBER REPORT

ROOF, R4

1 piece(s) 6 x 12 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2938 @ 1 1/4"	9453 (2.75")	Passed (31%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	2355 @ 1' 2 1/4"	8244	Passed (29%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	8480 @ 5' 11 3/4"	10166	Passed (83%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.139 @ 5' 11 3/4"	0.587	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.233 @ 5' 11 3/4"	0.783	Passed (L/606)		1.0 D + 1.0 S (All Spans)

Member Length: 12' 2 1/4"

System: Roof

Member Type: Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

Supports		Bearing Length			to Suppor		
	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	2.75"	2.75"	1.50"	1186	1753	2938	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	1227	1814	3041	Blocking

[•] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	12' 2" o/c	
Bottom Edge (Lu)	12' 2" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 12' 2 1/4"	N/A	16.0		
1 - Uniform (PLF)	0 to 12' 2" (Front)	N/A	56.3	90.6	Linked from: RJ2, Support 2
2 - Uniform (PLF)	0 to 12' 2" (Front)	N/A	126.0	202.5	Linked from: RJ3, Support 2

[·] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/ document-library.


ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



MEMBER REPORT PASSED

ROOF, R5

1 piece(s) 3 1/2" x 7 1/2" 24F-V4 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	4617 @ 10' 1 1/4"	5206 (3.50")	Passed (89%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	2296 @ 9' 4"	5333	Passed (43%)	1.15	1.0 D + 1.0 S (All Spans)
Pos Moment (Ft-lbs)	3658 @ 4' 4 1/16"	7547	Passed (48%)	1.15	1.0 D + 1.0 S (Alt Spans)
Neg Moment (Ft-lbs)	-4089 @ 10' 1 1/4"	5817	Passed (70%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.149 @ 4' 9 1/2"	0.489	Passed (L/786)		1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.242 @ 4' 9 5/16"	0.651	Passed (L/484)		1.0 D + 1.0 S (Alt Spans)

Member Length : 15' 5" System : Roof

Member Type: Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Critical positive moment adjusted by a volume/size factor of 1.00 that was calculated using length L = 8' 1/16".
- Critical negative moment adjusted by a volume/size factor of 1.00 that was calculated using length L = 5' 3 13/16".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- The specified glulam is assumed to have its strong laminations at the bottom of the beam. Install with proper side up as indicated by the manufacturer.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.50"	778	1201	1979	Blocking
2 - Stud wall - SPF	3.50"	3.50"	3.10"	1830	2787	4617	Blocking
3 - Stud wall - DF	3.50"	3.50"	1.50"	181	484/-72	665	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	15' 5" o/c	
Bottom Edge (Lu)	15' 5" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 15' 5"	N/A	6.4		
1 - Uniform (PLF)	0 to 15' 5" (Front)	N/A	174.5	275.5	Linked from: RJ3 Support 1

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC

ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

1 piece(s) 6 x 10 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1486 @ 4"	18906 (5.50")	Passed (8%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	907 @ 1' 3"	6810	Passed (13%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1914 @ 3' 2 1/2"	6937	Passed (28%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.013 @ 3' 2 1/2"	0.287	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.022 @ 3' 2 1/2"	0.383	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length : 6' 5" System : Roof

Member Type : Drop Beam Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD Member Pitch : 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.50"	602	884	1486	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	602	884	1486	Blocking

[•] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 5" o/c	
Bottom Edge (Lu)	6' 5" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 6' 5"	N/A	13.2		
1 - Uniform (PLF)	0 to 6' 5" (Front)	N/A	174.5	275.5	Linked from: RJ3 Support 1

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 6 x 10 DF No.2

Overall Length: 10' 8 1/4"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2262 @ 1 1/4"	9453 (2.75")	Passed (24%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	2167 @ 1' 1/4"	6810	Passed (32%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	6624 @ 3' 3"	6937	Passed (95%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.118 @ 4' 10 1/16"	0.512	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.203 @ 4' 10 3/16"	0.683	Passed (L/605)		1.0 D + 1.0 S (All Spans)

Member Length: 10' 8 1/4"

System: Roof

Member Type: Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	2.75"	2.75"	1.50"	942	1320	2262	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	553	742	1295	Blocking

[·] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	10' 8" o/c	
Bottom Edge (Lu)	10' 8" o/c	

Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 10' 8 1/4"	N/A	13.2		
1 - Uniform (PSF)	0 to 10' 8 1/4" (Front)	2'	15.0	25.0	Default Load
2 - Point (lb)	3' 3" (Front)	N/A	1033	1527	Linked from: R4, Support 1

Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava		
Nava Contracting and Engineering		
(503) 238-0633		
Mattsnava@gmail.com	1	



1 piece(s) 6 x 10 DF No.2

Overall Length: 12' 11 1/2"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	604 @ 1 1/4"	9453 (2.75")	Passed (6%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	509 @ 1' 1/4"	6810	Passed (7%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1895 @ 6' 5 3/4"	6937	Passed (27%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.058 @ 6' 5 3/4"	0.637	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.109 @ 6' 5 3/4"	0.850	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length: 12' 11 1/2" System : Roof

Member Type : Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

Supports	Carlo B	Bearing Length				Loads to Supports (lbs)			
	Total	Available	Required	Dead	Snow	Factored	Accessories		
1 - Stud wall - DF	2.75"	2.75"	1.50"	280	324	604	Blocking		
2 - Stud wall - DF	2.75"	2.75"	1.50"	280	324	604	Blocking		

[·] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	13' o/c	
Bottom Edge (Lu)	13' o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 12' 11 1/2"	N/A	13.2		
1 - Uniform (PSF)	0 to 12' 11 1/2" (Front)	2'	15.0	25.0	Default Load

[·] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/ document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 4 x 10 DF No.2

Overall Length: 5' 3"

Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1832 @ 0	3281 (1.50")	Passed (56%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	1207 @ 10 3/4"	4468	Passed (27%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	2404 @ 2' 7 1/2"	5166	Passed (47%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.018 @ 2' 7 1/2"	0.175	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.032 @ 2' 7 1/2"	0.262	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length: 5' 3" System: Wall Member Type : Header

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	802	604	769	1832	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	802	604	769	1832	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' 3" o/c	
Bottom Edge (Lu)	5' 3" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 5' 3"	N/A	8.2	111		
1 - Uniform (PSF)	0 to 5' 3"	11' 6"	10.0	20.0	-	CEILING
2 - Uniform (PLF)	0 to 5' 3"	N/A	56.3 - 9		90.6	Linked from: RJ2, Support 2
3 - Uniform (PLF)	0 to 5' 3"	N/A	126.0	-	202.5	Linked from: RJ3, Support 2


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/ document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 4 x 10 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2506 @ 0	3281 (1.50")	Passed (76%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	2427 @ 10 3/4"	4468	Passed (54%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	4054 @ 1' 8"	5166	Passed (78%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.036 @ 2' 10 3/8"	0.208	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.061 @ 2' 10 3/8"	0.313	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length : 6' 3" System : Wall Member Type : Header Building Use : Residential Building Code : IBC 2018

Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- · Applicable calculations are based on NDS.

Supports		Bearing Length			to Suppor		
	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	1019	1487	2506	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	447	640	1087	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 3" o/c	
Bottom Edge (Lu)	6' 3" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 6' 3"	N/A	8.2		
1 - Uniform (PSF)	0 to 6' 3"	2'	15.0	25.0	Default Load
2 - Point (lb)	1' 8"	N/A	1227	1814	Linked from: R5 Support 2

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 6 x 12 DF No.2

Overall Length: 7' 4 1/2"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	5593 @ 1 1/2"	10313 (3.00")	Passed (54%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	5477 @ 1' 2 1/2"	8244	Passed (66%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	8492 @ 1' 8"	10166	Passed (84%)	1.15	1.0 D + 1.0 S (All Spans)
Vert Live Load Defl. (in)	0.040 @ 3' 4 5/16"	0.242	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Vert Total Load Defl. (in)	0.068 @ 3' 4 3/8"	0.363	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Lat Member Reaction (lbs)	718 @ 7' 4 1/2"	N/A	Passed (N/A)	1.60	1.0 D + 0.6 W
Lat Shear (lbs)	602 @ 8 1/2"	11469	Passed (5%)	1.60	1.0 D + 0.6 W
Lat Moment (Ft-lbs)	1301 @ mid-span	6764	Passed (19%)	1.60	1.0 D + 0.6 W
Lat Deflection (in)	0.042 @ mid-span	0.363	Passed (L/999+)		1.0 D + 0.6 W
Bi-Axial Bending	0.66	1.00	Passed (66%)	1.60	1.0 D + 0.45 W + 0.75 L + 0.75 S

Member Length : 7' 4 1/2" System : Wall Member Type : Header Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Lateral deflection criteria: Wind (L/240)
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- Applicable calculations are based on NDS.

		Bearing Leng	th	Loads	to Suppor	ts (lbs)	
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Trimmer - DF	3.00"	3.00"	1.63"	2276	3317	5593	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	735	1027	1762	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	7' 5" o/c	
Bottom Edge (Lu)	7' 5" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Lateral Conr	ections					
Supports	Stud Size	Stud Material	Connector	Type/Model	Quantity	Nailing
Left	2X	Douglas Fir-Larch	Nails	10d (0.128" x 3") (End)	8	
Right	2X	Douglas Fir-Larch	Nails	10d (0.128" x 3") (End)	8	

Vertical Loads	Location	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 7' 4 1/2"	N/A	16.0		
1 - Uniform (PSF)	0 to 7' 4 1/2"	2'	15.0	25.0	Default Load
2 - Point (lb)	1' 8"	N/A	1689	2522	Linked from: R3, Support 1
3 - Point (lb)	1' 8"	N/A	983	1453	Linked from: R4, Support 2

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



			Wind	
Lateral Load	Location	Tributary Width	(1.60)	Comments
1 - Uniform (PSF)	Full Length	5' 6"	60.0	

[•] IBC Table 1604.3, footnote f: Deflection checks are performed using 42% of this lateral wind load.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



11/5/2024 9:39:46 PM UTC

ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3


File Name: McReynolds PC

MEMBER REPORT

ROOF, H4

1 piece(s) 6 x 10 DF No.2

Overall Length: 10' 9"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	501 @ 0	5156 (1.50")	Passed (10%)	T	1.0 D + 1.0 S (All Spans)
Shear (lbs)	416 @ 11"	6810	Passed (6%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1347 @ 5' 4 1/2"	6937	Passed (19%)	1.15	1.0 D + 1.0 S (All Spans)
Vert Live Load Defl. (in)	0.029 @ 5' 4 1/2"	0.358	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Vert Total Load Defl. (in)	0.055 @ 5' 4 1/2"	0.538	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Lat Member Reaction (lbs)	871 @ 10' 9"	N/A	Passed (N/A)	1.60	1.0 D + 0.6 W
Lat Shear (lbs)	776 @ 7"	9475	Passed (8%)	1.60	1.0 D + 0.6 W
Lat Moment (Ft-lbs)	2340 @ mid-span	5588	Passed (42%)	1.60	1.0 D + 0.6 W
Lat Deflection (in)	0.199 @ mid-span	0.538	Passed (L/648)		1.0 D + 0.6 W
Bi-Axial Bending	0.48	1.00	Passed (48%)	1.60	1.0 D + 0.6 W

Member Length: 10' 9" System: Wall Member Type : Header Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Lateral deflection criteria: Wind (L/240)
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

	В	Bearing Length			to Suppor			
Supports	Total	Available Required		Dead Snow		Factored	Accessories	
1 - Trimmer - DF	1.50"	1.50"	1.50"	232	269	501	None	
2 - Trimmer - DF	1.50"	1.50"	1.50"	232	269	501	None	

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	10' 9" o/c	
Bottom Edge (Lu)	10' 9" o/c	

Maximum allowable bracing intervals based on applied load.

Lateral Connections								
Supports	Stud Size	Stud Material	Connector	Type/Model	Quantity	Nailing		
Left	2X	Douglas Fir-Larch	Nails	16d (0.135" x 3 1/2") (End)	8			
Right	2X	Douglas Fir-Larch	Nails	16d (0.135" x 3 1/2") (End)	8			

Vertical Loads	Location	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 10' 9"	N/A	13.2		
1 - Uniform (PSF)	0 to 10' 9"	2'	15.0	25.0	Default Load


			Wind	
Lateral Load	Location	Tributary Width	(1.60)	Comments
1 - Uniform (PSF)	Full Length	4' 6"	60.0	

able 1604.3, footnote f: Deflection checks are performed using 42% of this lateral wind load.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 6 x 10 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1534 @ 0	5156 (1.50")	Passed (30%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	1117 @ 11"	6810	Passed (16%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	2588 @ 3' 4 1/2"	6937	Passed (37%)	1.15	1.0 D + 1.0 S (All Spans)
Vert Live Load Defl. (in)	0.025 @ 3' 4 1/2"	0.225	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Vert Total Load Defl. (in)	0.042 @ 3' 4 1/2"	0.338	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Lat Member Reaction (lbs)	547 @ 6' 9"	N/A	Passed (N/A)	1.60	1.0 D + 0.6 W
Lat Shear (lbs)	452 @ 7"	9475	Passed (5%)	1.60	1.0 D + 0.6 W
Lat Moment (Ft-lbs)	923 @ mid-span	5588	Passed (17%)	1.60	1.0 D + 0.6 W
Lat Deflection (in)	0.031 @ mid-span	0.338	Passed (L/999+)		1.0 D + 0.6 W
Bi-Axial Bending	0.35	1.00	Passed (35%)	1.60	1.0 D + 0.45 W + 0.75 L + 0.75 S

Member Length : 6' 9" System : Wall Member Type : Header Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Lateral deflection criteria: Wind (L/240)
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- Applicable calculations are based on NDS.

Supports		Bearing Length			to Support		
	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	610	924	1534	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	610	924	1534	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 9" o/c	
Bottom Edge (Lu)	6' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Lateral Connections								
Supports	Stud Size	Stud Material	Connector	Type/Model	Quantity	Nailing		
Left	2X	Douglas Fir-Larch	Nails	10d (0.128" x 3") (End)	6			
Right	2X	Douglas Fir-Larch	Nails	10d (0.128" x 3") (End)	6			

Vertical Loads	Location	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 6' 9"	N/A	13.2		
1 - Uniform (PLF)	0 to 6' 9"	N/A	56.3	90.6	Linked from: RJ2, Support 2
2 - Uniform (PLF)	0 to 6' 9"	N/A	111.2	183.1	Linked from: RJ1, Support 2


			Wind (1.60)	
Lateral Load	Location	Tributary Width		Comments
1 - Uniform (PSF)	Full Length	4' 6"	60.0	

ForteWEB Software Operator	Job Notes
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com	



1 piece(s) 4 x 10 DF No.2

Overall Length: 6' 9"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1435 @ 0	3281 (1.50")	Passed (44%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	1054 @ 10 3/4"	4468	Passed (24%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	2421 @ 3' 4 1/2"	5166	Passed (47%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.033 @ 3' 4 1/2"	0.225	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.054 @ 3' 4 1/2"	0.338	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length : 6' 9" System : Wall Member Type : Header

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- · Applicable calculations are based on NDS.

		Bearing Length			to Suppor		
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	566	869	1435	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	566	869	1435	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 9" o/c	
Bottom Edge (Lu)	6' 9" o/c	

Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 6' 9"	N/A	8.2		
1 - Uniform (PLF)	0 to 6' 9"	N/A	159.4	257.5	Linked from: RJ1, Support 1

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava		
Nava Contracting and Engineering		
(503) 238-0633		
Mattsnava@gmail.com		
Mattsnava@gmail.com		



ROOF, C1 1 piece(s) 6 x 8 DF No.2

Overall Length: 3' 10 1/2"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	4108 @ 3' 6 1/2"	18906 (5.50")	Passed (22%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	568 @ 2' 9 1/2"	5376	Passed (11%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	853 @ 3' 4"	3706	Passed (23%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.003 @ 2' 3/4"	0.169	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.005 @ 2' 9/16"	0.225	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length: 3' 10 1/2"

System: Roof

Member Type : Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- · Applicable calculations are based on NDS.

		Bearing Leng	th	Loads to Supports (lbs)			Greek et s	
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	3.50"	3.50"	1.50"	163	74	159	338	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	1685	81	2424	4108	Blocking

[·] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	3' 11" o/c	
Bottom Edge (Lu)	3' 11" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 3' 10 1/2"	N/A	10.4			
1 - Uniform (PSF)	0 to 3' 10 1/2" (Front)	2'	10.0	20.0	-	ATTIC
2 - Point (lb)	3' 4" (Front)	N/A	1730	-	2583	Linked from: R3, Support 2

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/ document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 2 x 8 DF No.2 @ 24" OC

12'6"

Overall Length: 13'3"

Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	258 @ 13' 1/2"	2109 (2.25")	Passed (12%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	226 @ 1' 3/4"	1305	Passed (17%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	802 @ 6' 8 1/2"	1360	Passed (59%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.152 @ 6' 8 1/2"	0.317	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.304 @ 6' 8 1/2"	0.633	Passed (L/500)		1.0 D + 1.0 L (All Spans)
TJ-Pro™ Rating	N/A	N/A	N/A		N/A

Member Length: 13' 1/2" System: Floor Member Type: Joist Building Use: Residential

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- Applicable calculations are based on NDS.
- No composite action between deck and joist was considered in analysis.

		Bearing Length			ds to Supports		
Supports	Total	Available	Required	Dead	Floor Live	Factored	Accessories
1 - Stud wall - DF	5.50"	4.25"	1.50"	134	134	268	1 1/4" Rim Board
2 - Stud wall - DF	3.50"	2.25"	1.50"	131	131	262	1 1/4" Rim Board

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	12' 5" o/c	
Bottom Edge (Lu)	13' 1" o/c	

Maximum allowable bracing intervals based on applied load.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Floor Live (1.00)	Comments
1 - Uniform (PSF)	0 to 13' 3"	24"	10.0	10.0	Default Load

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava		
Nava Contracting and Engineering (503) 238-0633		
Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC

ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

1 piece(s) 2 x 8 DF No.2 @ 24" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	752 @ 3' 7 3/4"	3506 (5.50")	Passed (21%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	349 @ 4' 5 3/4"	1305	Passed (27%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	-1037 @ 3' 7 3/4"	1360	Passed (76%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.191 @ 12' 5 5/16"	0.395	Passed (L/995)		1.0 D + 1.0 L (Alt Spans)
Total Load Defl. (in)	0.380 @ 12' 5 3/8"	0.791	Passed (L/500)		1.0 D + 1.0 L (Alt Spans)
TJ-Pro™ Rating	N/A	N/A	N/A		N/A

Member Length: 19' 8 3/4"

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- -262 lbs uplift at support located at 2 1/2". Strapping or other restraint may be required.
- · Applicable calculations are based on NDS.
- No composite action between deck and joist was considered in analysis.

		Bearing Length		Loa	ds to Supports		
Supports	Total	Available	Required	Dead	Floor Live	Factored	Accessories
1 - Stud wall - DF	3.50"	3.50"	1.50"	-112	37/-149	-262	Blocking
2 - Stud wall - SPF	5.50"	5.50"	1.50"	376	376	752	None
3 - Stud wall - DF	5.50"	4.25"	1.50"	133	133	266	1 1/4" Rim Board

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.
- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	12' 9" o/c	
Bottom Edge (Lu)	8' 11" o/c	

Maximum allowable bracing intervals based on applied load.

Vertical Load	Lauren (Cida)	Spacing	Dead (0.90)	Floor Live	
vertical Load	Location (Side)	Spacing	(0.90)	(1.00)	Comments
1 - Uniform (PSF)	0 to 19' 10"	24"	10.0	10.0	Default Load

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 2 x 8 DF No.2 @ 24" OC

Overall Length: 16' 5 9/16"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	403 @ 9' 2 1/4"	2231 (3.50")	Passed (18%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	186 @ 8' 5 1/4"	1305	Passed (14%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	-331 @ 9' 2 1/4"	1360	Passed (24%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.025 @ 4' 5 3/16"	0.224	Passed (L/999+)		1.0 D + 1.0 L (Alt Spans)
Total Load Defl. (in)	0.045 @ 4' 4 1/16"	0.449	Passed (L/999+)		1.0 D + 1.0 L (Alt Spans)
TJ-Pro™ Rating	N/A	N/A	N/A		N/A

Member Length : 16' 4 5/16"

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.
- No composite action between deck and joist was considered in analysis.

		Bearing Length			ds to Supports		
Supports	Total	Available	Required	Dead	Floor Live	Factored	Accessories
1 - Stud wall - DF	3.50"	3.50"	1.50"	76	81/-6	157	Blocking
2 - Stud wall - SPF	3.50"	3.50"	1.50"	201	201	403	None
3 - Stud wall - DF	5.50"	4.25"	1.50"	52	69/-14	121	1 1/4" Rim Board

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.
- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	16' 4" o/c	
Bottom Edge (Lu)	16' 4" o/c	

[•]Maximum allowable bracing intervals based on applied load.

			Dead	Floor Live	
Vertical Load	Location (Side)	Spacing	(0.90)	(1.00)	Comments
1 - Uniform (PSF)	0 to 16' 5 9/16"	24"	10.0	10.0	Default Load


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 2 x 8 DF No.2 @ 24" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	151 @ 7' 8 1/2"	2109 (2.25")	Passed (7%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	119 @ 1' 3/4"	1305	Passed (9%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	269 @ 4' 1/2"	1360	Passed (20%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.017 @ 4' 1/2"	0.183	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.034 @ 4' 1/2"	0.367	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
TJ-Pro™ Rating	N/A	N/A	N/A		N/A

Member Length: 7' 9 3/4"

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- Applicable calculations are based on NDS.
- No composite action between deck and joist was considered in analysis.

	Bearing Length			Loa	ds to Supports		
Supports	Total	Available	Required	Dead	Floor Live	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.50"	81	81	162	Blocking
2 - Stud wall - DF	3.50"	2.25"	1.50"	78	78	155	1 1/4" Rim Board

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.
- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	7' 10" o/c	
Bottom Edge (Lu)	7' 10" o/c	

Maximum allowable bracing intervals based on applied load.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Floor Live (1.00)	Comments
1 - Uniform (PSF)	0 to 7' 11"	24"	10.0	10.0	Default Load

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 document-library.


ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



ROOF, R2 (not used disregard)

1 piece(s) 6 x 12 DF No.2





Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1153 @ 1 1/4"	9453 (2.75")	Passed (12%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	610 @ 1' 2 1/4"	8244	Passed (7%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	1335 @ 2' 6 1/4"	10166	Passed (13%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.004 @ 2' 6 1/4"	0.242	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.006 @ 2' 6 1/4"	0.322	Passed (L/999+)		1.0 D + 1.0 S (All Spans)

Member Length: 5' 3 1/4"

System: Roof

Member Type : Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	2.75"	2.75"	1.50"	463	690	1153	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	501	747	1248	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' 3" o/c	
Bottom Edge (Lu)	5' 3" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 5' 3 1/4"	N/A	16.0		
1 - Uniform (PLF)	0 to 5' 3" (Front)	N/A	111.2	183.1	Linked from: RJ1, Support 2
2 - Uniform (PLF)	0 to 5' 3" (Front)	N/A	56.3	90.6	Linked from: RJ2, Support 1

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties weyernaeuser warrants that the sizing of its products will be in accordance with weyernaeuser product design criteria and published design values. Weyernaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, FJ1

1 piece(s) 14" TJI® 360 @ 16" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)	
Member Reaction (lbs)	814 @ 25' 7 1/2"	1505 (3.50")	Passed (54%)	1.00	1.0 D + 1.0 L (Alt Spans)	
Shear (lbs)	790 @ 25' 6 1/2"	1955	Passed (40%)	1.00	1.0 D + 1.0 L (Alt Spans)	
Moment (Ft-lbs)	4564 @ 14' 1 13/16"	7335	Passed (62%)	1.00	1.0 D + 1.0 L (Alt Spans)	
Live Load Defl. (in)	0.539 @ 13' 11 1/8"	0.585	Passed (L/521)		1.0 D + 1.0 L (Alt Spans)	
Total Load Defl. (in)	0.672 @ 14' 1/16"	1.170	Passed (L/418)		1.0 D + 1.0 L (Alt Spans)	
TJ-Pro™ Rating	42	40	Passed			

Member Length: 25' 10 3/4"

System: Floor Member Type : Joist Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Overhang deflection criteria: LL (2L/480) and TL (2L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A structural analysis of the deck has not been performed.
- Deflection analysis is based on composite action with a single layer of 7/8" Weyerhaeuser Edge Gold™ Panel (32" Span Rating) that is glued and nailed down.
- Additional considerations for the TJ-Pro™ Rating include: 5/8" Gypsum ceiling.

第115年2月198日 1988	Bearing Length			Loads to Supports (lbs)				
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	3.50"	392	748	73	1140	Blocking
2 - Stud wall - DF	5.50"	4.25"	1.75"	178	644	-6	822	1 1/4" Rim Board

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.
- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	4' 9" o/c	
Bottom Edge (Lu)	9' 7" o/c	

- •TJI joists are only analyzed using Maximum Allowable bracing solutions.
- Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Spacing	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 26'	16"	12.0	40.0	-	Default Load
2 - Point (PLF)	1 1/2"	16"	85.0	-	-	
3 - Point (PLF)	1 1/2"	16"	30.0	-	50.0	

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/ document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, FJ2 1 piece(s) 14" TJI® 360 @ 16" OC

Overall Length: 14'11"

Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	510 @ 4 1/2"	1505 (3.50")	Passed (34%)	1.00	1.0 D + 1.0 L (All Spans)
Shear (lbs)	485 @ 5 1/2"	1955	Passed (25%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	1739 @ 7' 5 1/2"	7335	Passed (24%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.085 @ 7' 5 1/2"	0.354	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.111 @ 7' 5 1/2"	0.708	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
TJ-Pro™ Rating	64	40	Passed		

Member Length : 14' 8 1/2" System : Floor

System: Floor
Member Type: Joist
Building Use: Residential
Building Code: IBC 2018
Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A structural analysis of the deck has not been performed.
- Deflection analysis is based on composite action with a single layer of 7/8" Weyerhaeuser Edge Gold™ Panel (32" Span Rating) that is glued and nailed down.
- Additional considerations for the TJ-Pro™ Rating include: 5/8" Gypsum ceiling.

		Loa	ds to Supports					
Supports	Total	Available	Required	Dead	Dead Floor Live		Accessories	
1 - Stud wall - DF	5.50"	4.25"	1.75"	119	398	517	1 1/4" Rim Board	
2 - Stud wall - DF	5.50"	4.25"	1.75"	119	398	517	1 1/4" Rim Board	

[•] Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	7' 11" o/c	
Bottom Edge (Lu)	14' 9" o/c	

[•]TJI joists are only analyzed using Maximum Allowable bracing solutions.

Maximum allowable bracing intervals based on applied load.

Vertical Load	Location	Spacing	Dead (0.90)	Floor Live (1.00)	Comments
1 - Uniform (PSF)	0 to 14' 11"	16"	12.0	40.0	Default Load

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, FJ3

1 piece(s) 14" TJI® 210 @ 16" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)		
Member Reaction (lbs)	1264 @ 20' 5 1/2"	1264 (2.12")	Passed (100%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)		
Shear (lbs)	1264 @ 20' 5 1/2"	2237	Passed (57%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)		
Moment (Ft-lbs)	4346 @ 11' 6 7/8"	4490	4490 Passed (97%)		1.0 D + 1.0 L (All Spans)		
Live Load Defl. (in)	0.398 @ 10' 9 1/2"	0.502	Passed (L/606)		1.0 D + 0.75 L + 0.75 S (All Spans)		
Total Load Defl. (in)	0.639 @ 10' 11"	1.004	Passed (L/377)		1.0 D + 0.75 L + 0.75 S (All Spans)		
TJ-Pro™ Rating	49	40	Passed				

Member Length : 20' 4 1/4"

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- · A structural analysis of the deck has not been performed.
- Deflection analysis is based on composite action with a single layer of 7/8" Weyerhaeuser Edge Gold™ Panel (32" Span Rating) that is glued and nailed down.
- Additional considerations for the TJ-Pro $^{\text{\tiny TM}}$ Rating include: 5/8" Gypsum ceiling.

	Bearing Length			Loads to Supports (lbs)				
Supports	Total Available	Available	Required	Required Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	4.25"	1.75"	247	556	96	802	1 1/4" Rim Board
2 - Hanger on 14" DF beam	3.50"	Hanger ¹	2.12" / - 2	534	551	444	1281	See note 1

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- ¹ See Connector grid below for additional information and/or requirements.
- ² Required Bearing Length / Required Bearing Length with Web Stiffeners

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	3' 8" o/c	
Bottom Edge (Lu)	20' 4" o/c	

- •TJI joists are only analyzed using Maximum Allowable bracing solutions.
- •Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie										
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories				
2 - Face Mount Hanger	HU2.1/9	2.50"	N/A	14-10dx1.5	6-10dx1.5	Web Stiffeners				

Refer to manufacturer notes and instructions for proper installation and use of all connectors.


Vertical Loads	Location	Spacing	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 20' 9"	16"	12.0	40.0	-	Default Load
2 - Point (PLF)	16' 10 1/2"	16"	126.0	-	202.5	Linked from: RJ3, Support 2
3 - Point (PLF)	16' 10 1/2"	16"	125.6	-	203.1	Linked from: RJ4, Support 2
4 - Point (PLF)	16' 10 1/2"	16"	85.0	-	-	WALL WEIGHT

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, FJ4

1 piece(s) 14" TJI® 360 @ 16" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	298 @ 5 1/2"	1080 (1.75")	Passed (28%)	1.00	1.0 D + 1.0 L (Alt Spans)
Shear (lbs)	359 @ 9' 11 1/2"	1955	Passed (18%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	641 @ 4' 9 1/16"	7335	Passed (9%)	1.00	1.0 D + 1.0 L (Alt Spans)
Live Load Defl. (in)	0.024 @ 5' 3 7/8"	0.243	Passed (L/999+)		1.0 D + 1.0 L (Alt Spans)
Total Load Defl. (in)	0.018 @ 12' 5"	0.223	Passed (2L/999+)		1.0 D + 0.75 L + 0.75 S (Alt Spans)
TJ-Pro™ Rating	69	40	Passed		

Member Length: 11' 11 1/2"

System: Floor Member Type : Joist Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Overhang deflection criteria: LL (2L/480) and TL (2L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A structural analysis of the deck has not been performed.
- Deflection analysis is based on composite action with a single layer of 7/8" Weyerhaeuser Edge Gold™ Panel (32" Span Rating) that is glued and nailed down.
- Additional considerations for the TJ-Pro™ Rating include: 1/2" Gypsum ceiling.

		Bearing Length			Loads to Sup			
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Hanger on 14" DF beam	5.50"	Hanger ¹	1.75" / - 2	46	284	-15	330	See note ¹
2 - Stud wall - DF	5.50"	5.50"	3.50"	306	392	82	698	Blocking

- · Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- 1 See Connector grid below for additional information and/or requirements.
- $\bullet\,\,^{\rm 2}$ Required Bearing Length / Required Bearing Length with Web Stiffeners

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 7" o/c	
Bottom Edge (Lu)	9' 7" o/c	

- •TJI joists are only analyzed using Maximum Allowable bracing solutions.
- •Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie									
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories			
1 - Face Mount Hanger	IUS2.37/14	2.00"	N/A	12-10dx1.5	2-Strong-Grip				

[•] Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location	Spacing	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 12' 5"	16"	12.0	40.0	-	Default Load
2 - Point (PLF)	12' 4"	16"	85.0	-	-	
3 - Point (PLF)	12' 4"	16"	30.0	-	50.0	

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, B1

2 piece(s) 1 1/2" x 14" 1.5E TimberStrand® LSL

Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	3324 @ 5 1/2"	3870 (1.50")	Passed (86%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	2189 @ 1' 7 1/2"	9660	Passed (23%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	5679 @ 3' 10 1/2"	20834	Passed (27%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.039 @ 3' 10 1/2"	0.171	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.067 @ 3' 10 1/2"	0.342	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 6' 10" System : Floor Member Type : Flush Beam

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.

Supports	Bearing Length				Loads to Sup			
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Hanger on 14" DF beam	5.50"	Hanger ¹	1.50"	1596	1601	1290	3765	See note 1
2 - Hanger on 14" DF beam	5.50"	Hanger ¹	1.50"	1595	1601	1290	3764	See note 1

- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- ¹ See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 10" o/c	
Bottom Edge (Lu)	6' 10" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie							
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories	
1 - Face Mount Hanger	HHUS210-2	3.00"	N/A	30-10d	10-10d		
2 - Face Mount Hanger	HHUS210-2	3.00"	N/A	30-10d	10-10d		

Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	5 1/2" to 7' 3 1/2"	N/A	12.8			
1 - Uniform (PLF)	0 to 7' 9" (Front)	N/A	400.5	413.3	333.0	Linked from: FJ3 Support 2

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes		
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com			



Page 37 / 67

1 piece(s) 7" x 14" 2.2E Parallam® PSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	6997 @ 23' 8"	17500 (4.00")	Passed (40%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	6867 @ 22' 4 1/2"	21789	Passed (32%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	31755 @ 16' 10 1/2"	62472	Passed (51%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.418 @ 13' 4"	0.583	Passed (L/670)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.796 @ 13' 1/16"	1.167	Passed (L/352)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Member should be side-loaded from both sides of the member or braced to prevent rotation.

	Maria E	Bearing Length			Loads to Sup				
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories	
1 - Stud wall - DF	5.50"	4.00"	1.50"	1335	914	951	2734	1 1/2" Rim Board	
2 - Stud wall - DF	5.50"	4.00"	1.60"	3221	2123	2922	7004	1 1/2" Rim Board	

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	30.6			
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	-	Default Load
2 - Point (lb)	20' 6" (Front)	N/A	1596	1601	1290	Linked from: B1, Support 1
3 - Point (lb)	13' 4" (Front)	N/A	163	74	159	Linked from: C1, Support 1
4 - Point (Ib)	16' 10 1/2" (Front)	N/A	1685	81	2424	Linked from: C1, Support 2

Side loads are assumed to not induce cross-grain tension.


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, B2 with Strap Wind Down 1 piece(s) 7" x 14" 2.2E Parallam® PSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	7874 @ 23' 8"	17500 (4.00")	Passed (45%)		1.0 D + 0.45 W + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	6867 @ 22' 4 1/2"	21789	Passed (32%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	31755 @ 16' 10 1/2"	62472	Passed (51%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.549 @ 13' 4"	0.583	Passed (L/510)		1.0 D + 0.45 W + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.927 @ 13' 7/16"	1.167	Passed (L/302)		1.0 D + 0.45 W + 0.75 L + 0.75 S (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam

Member Type: Flush Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Member should be side-loaded from both sides of the member or braced to prevent rotation.

Supports	В	Bearing Length			Loads to Supports (lbs)					
	Total	Available	Required	Dead	Floor Live	Snow	Wind	Seismic	Factored	Accessories
1 - Stud wall - DF	5.50"	4.00"	1.50"	1335	914	951	800	523/-523	3094	1 1/2" Rim Board
2 - Stud wall - DF	5.50"	4.00"	1.80"	3221	2123	2922	1950	1273/-127 3	7881	1 1/2" Rim Board

[•] Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Wind (1.60)	Seismic (1.60)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	30.6		198427			
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	12	-	-	Default Load
2 - Point (lb)	20' 6" (Front)	N/A	1596	1601	1290	-	2	Linked from: B1, Support 1
3 - Point (lb)	16' 10 1/2" (Front)	N/A	-	-	-	2750	1796	
4 - Point (lb)	13' 4" (Front)	N/A	163	74	159	s -	H	Linked from: R6, Support 1
5 - Point (lb)	16' 10 1/2" (Front)	N/A	1685	81	2424	-	-	Linked from: R6, Support 2

Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC

ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

FLOOR, B2 with Strap Wind Up

1 piece(s) 7" x 14" 2.2E Parallam® PSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	7665 @ 23' 8"	17500 (4.00")	Passed (44%)		1.0 D - 0.525 E + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	6867 @ 22' 4 1/2"	21789	Passed (32%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	31755 @ 16' 10 1/2"	62472	Passed (51%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.418 @ 13' 4"	0.583	Passed (L/670)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.796 @ 13' 1/16"	1.167	Passed (L/352)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length: 23' 9" System: Floor Member Type: Flush Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Member should be side-loaded from both sides of the member or braced to prevent rotation.

Supports	Bearing Length				Loads to Supports (lbs)					
	Total	Available	Required	Dead	Floor Live	Snow	Wind	Seismic	Factored	Accessories
1 - Stud wall - DF	5.50"	4.00"	1.50"	1335	914	951	-800	523/-523	3008	1 1/2" Rim Board
2 - Stud wall - DF	5.50"	4.00"	1.75"	3221	2123	2922	-1950	1273/-127 3	7672	1 1/2" Rim Board

[•] Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Wind (1.60)	Seismic (1.60)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	30.6					
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	-	-	-	Default Load
2 - Point (lb)	20' 6" (Front)	N/A	1596	1601	1290	-	-	Linked from: B1, Support 1
3 - Point (lb)	16' 10 1/2" (Front)	N/A	-	-	2	-2750	-1796	
4 - Point (lb)	13' 4" (Front)	N/A	163	74	159	-	-	Linked from: R6, Support 1
5 - Point (lb)	16' 10 1/2" (Front)	N/A	1685	81	2424	-	-	Linked from: R6, Support 2

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633		
Mattsnava@gmail.com		






MEMBER REPORT

FLOOR, B2 with Overstrength

1 piece(s) 7" x 14" 2.2E Parallam® PSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	8668 @ 23' 8"	17500 (4.00")	Passed (50%)		1.0 D + 0.525 E + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	6867 @ 22' 4 1/2"	21789	Passed (32%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	31755 @ 16' 10 1/2"	62472	Passed (51%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.418 @ 13' 4"	0.583	Passed (L/670)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.796 @ 13' 1/16"	1.167	Passed (L/352)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC 2018

Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- -295 lbs uplift at support located at 23' 8". Strapping or other restraint may be required.
- Member should be side-loaded from both sides of the member or braced to prevent rotation.

Supports	DEPOSIT INTEREST	Bearing Length			Loads to Supports (lbs)					
	Total	Available	Required	Dead	Floor Live	Snow	Seismic	Factored	Accessories	
1 - Stud wall - DF	5.50"	4.00"	1.50"	1335	914	951	1307/-130 7	3420/-114	1 1/2" Rim Board	
2 - Stud wall - DF	5.50"	4.00"	1.98"	3221	2123	2922	3182/-318 2	8675/-295	1 1/2" Rim Board	

[•] Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Seismic (1.60)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	30.6				
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	-	-	Default Load
2 - Point (lb)	20' 6" (Front)	N/A	1596	1601	1290	-	Linked from: B1, Support 1
3 - Point (lb)	16' 10 1/2" (Front)	N/A	-	-	-	4489	
4 - Point (lb)	13' 4" (Front)	N/A	163	74	159	-	Linked from: R6, Support 1
5 - Point (Ib)	16' 10 1/2" (Front)	N/A	1685	81	2424	-	Linked from: R6, Support 2

Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		w



11/5/2024 9:39:46 PM UTC ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

1 piece(s) 5 1/4" x 14" 2.2E Parallam® PSL

Overall Length: 24'

Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	5489 @ 23' 8"	13125 (4.00")	Passed (42%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	4717 @ 22' 4 1/2"	14210	Passed (33%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	19131 @ 16' 10 1/2"	40743	Passed (47%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.407 @ 13' 13/16"	0.583	Passed (L/688)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.737 @ 13' 5/16"	1.167	Passed (L/380)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.

Supports		Bearing Length			Loads to Sup			
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	4.00"	1.50"	915	1033	399	1989	1 1/2" Rim Board
2 - Stud wall - DF	5.50"	4.00"	1.67"	2412	2452	1660	5496	1 1/2" Rim Board

• Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	23.0			
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	-	Default Load
2 - Point (lb)	20' 6" (Front)	N/A	1595	1601	1290	Linked from: B1, Support 2
3 - Point (lb)	16' 10 1/2" (Front)	N/A	802	604	769	Linked from: H1, Support 1

[·] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, B3 with Strap Wind Down

1 piece(s) 5 1/4" x 14" 2.2E Parallam® PSL





Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	6366 @ 23' 8"	13125 (4.00")	Passed (49%)		1.0 D + 0.45 W + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	4717 @ 22' 4 1/2"	14210	Passed (33%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	19131 @ 16' 10 1/2"	40743	Passed (47%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.581 @ 13' 1 3/8"	0.583	Passed (L/482)		1.0 D + 0.45 W + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.912 @ 13' 13/16"	1.167	Passed (L/307)		1.0 D + 0.45 W + 0.75 L + 0.75 S (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.

		Bearing Length			Loads to Supports (lbs)					
Supports	Total	Available	Required	Dead	Floor Live	Snow	Wind	Seismic	Factored	Accessories
1 - Stud wall - DF	5.50"	4.00"	1.50"	915	1033	399	800	523/-523	2349	1 1/2" Rim Board
2 - Stud wall - DF	5.50"	4.00"	1.94"	2412	2452	1660	1950	1273/-127 3	6373	1 1/2" Rim Board

Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Wind (1.60)	Seismic (1.60)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	23.0					
1 - Uniform (PSF)	' 0 to 24' (Front)	1' 4"	12.0	40.0	2	-	-	Default Load
2 - Point (lb)	20' 6" (Front)	N/A	1595	1601	1290	-	1(=)	Linked from: B1, Support 2
3 - Point (lb)	16' 10 1/2" (Front)	N/A	802	604	769	-	3-	Linked from: H1, Support 1
4 - Point (lb)	16' 10 1/2" (Front)	N/A	-	-	-	2750	1796	

Side loads are assumed to not induce cross-grain tension.


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, B3 with Strap Wind Up 1 piece(s) 5 1/4" x 14" 2.2E Parallam® PSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	6158 @ 23' 8"	13125 (4.00")	Passed (47%)		1.0 D - 0.525 E + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	4717 @ 22' 4 1/2"	14210	Passed (33%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	19131 @ 16' 10 1/2"	40743	Passed (47%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.407 @ 13' 13/16"	0.583	Passed (L/688)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.737 @ 13' 5/16"	1.167	Passed (L/380)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam Building Use : Residential Building Code : IBC 2018

Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.

《 图》	В	Bearing Length			Loads to Supports (lbs)					
Supports	Total	Available	Required	Dead	Floor Live	Snow	Wind	Seismic	Factored	Accessories
1 - Stud wall - DF	5.50"	4.00"	1.50"	915	1033	399	-800	523/-523	2263	1 1/2" Rim Board
2 - Stud wall - DF	5.50"	4.00"	1.88"	2412	2452	1660	-1950	1273/-127 3	6165	1 1/2" Rim Board

• Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

•Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Wind (1.60)	Seismic (1.60)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	23.0					
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	-	-	-	Default Load
2 - Point (lb)	20' 6" (Front)	N/A	1595	1601	1290	-	-	Linked from: B1, Support 2
3 - Point (lb)	16' 10 1/2" (Front)	N/A	802	604	769	-	-	Linked from: H1, Support 1
4 - Point (lb)	16' 10 1/2" (Front)	N/A	-	-	-	-2750	-1796	

[•] Side loads are assumed to not induce cross-grain tension.


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, B3 with Overstrength 1 piece(s) 5 1/4" x 14" 2.2E Parallam® PSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	7160 @ 23' 8"	13125 (4.00")	Passed (55%)		1.0 D + 0.525 E + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	4717 @ 22' 4 1/2"	14210	Passed (33%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	33052 @ 16' 10 1/2"	65188	Passed (51%)	1.60	1.0 D + 0.525 E + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.407 @ 13' 13/16"	0.583	Passed (L/688)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.737 @ 13' 5/16"	1.167	Passed (L/380)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam Building Use : Residential

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- -366 lbs uplift at support located at 4". Strapping or other restraint may be required.
- -781 lbs uplift at support located at 23' 8". Strapping or other restraint may be required.

	В	Bearing Length			Loads to Supports (lbs)					
Supports	Total	Available	Required	Dead	Floor Live	Snow	Seismic	Factored	Accessories	
1 - Stud wall - DF	5.50"	4.00"	1.50"	915	1033	399	1307/-130 7	2675/-366	1 1/2" Rim Board	
2 - Stud wall - DF	5.50"	4.00"	2.18"	2412	2452	1660	3182/-318 2	7167/-781	1 1/2" Rim Board	

[•] Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Seismic (1.60)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	23.0				
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	-	-	Default Load
2 - Point (Ib)	20' 6" (Front)	N/A	1595	1601	1290	-	Linked from: B1, Support 2
3 - Point (lb)	16' 10 1/2" (Front)	N/A	802	604	769	-	Linked from: H1, Support 1
4 - Point (lb)	16' 10 1/2" (Front)	N/A	-	-	-	4489	

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

2 piece(s) 14" TJI® 360 @ 16" OC

An excessive uplift of 522 lbs at support located at 5 1/2" failed this product.

Passed MIU Hanger At Reaction 1



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	3447 @ 10' 2 1/4"	6900 (5.25")	Passed (50%)	1.15	1.0 D + 1.0 S (All Spans)
Shear (lbs)	2758 @ 10' 5"	4497	Passed (61%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	-5908 @ 10' 2 1/4"	16871	Passed (35%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.062 @ 12' 5"	0.200	Passed (2L/856)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.109 @ 12' 5"	0.223	Passed (2L/492)		1.0 D + 1.0 S (All Spans)
TJ-Pro™ Rating	72	40	Passed		

Member Length : 11' 11 1/2"

System : Floor Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Overhang deflection criteria: LL (0.2") and TL (2L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- · A structural analysis of the deck has not been performed.
- Deflection analysis is based on composite action with a single layer of 7/8" Weyerhaeuser Edge Gold™ Panel (32" Span Rating) that is glued and nailed down.
- \bullet Additional considerations for the TJ-Pro $^{\text{\tiny{TM}}}$ Rating include: 1/2" Gypsum ceiling.

	in the B	Bearing Leng	th decision	466	Loads to Sup			
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Hanger on 14" DF beam	5.50"	Hanger ¹	1.75" / - 2	-179	284	-343	105/-522	See note 1
2 - Stud wall - DF	5.50"	5.50"	3.50"	1550	392	1897	3447	Blocking

- Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- \bullet $^{\rm 1}$ See Connector grid below for additional information and/or requirements.
- ² Required Bearing Length / Required Bearing Length with Web Stiffeners

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 7" o/c	
Bottom Edge (Lu)	6' 1" o/c	

- •TJI joists are only analyzed using Maximum Allowable bracing solutions.
- •Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-1	rie de la company					
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories
1 - Face Mount Hanger	MIU4.75/9	2.50"	N/A	16-10dx1.5	6-10dx1.5	Web Stiffeners


[•] Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Loads	Location	Spacing	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 12' 5"	16"	12.0	40.0	-	Default Load
2 - Point (PLF)	12' 4"	16"	85.0	15	-	
3 - Point (PLF)	12' 4"	16"	30.0	-	50.0	
4 - Point (lb)	12' 4"	N/A	1019	-	1487	Linked from: H2 Support 1

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 7" x 14" 2.2E Parallam® PSL



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	6168 @ 23' 8"	17500 (4.00")	Passed (35%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	5508 @ 22' 4 1/2"	18947	Passed (29%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	33820 @ 14' 3 7/16"	54324	Passed (62%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.622 @ 12' 2"	0.778	Passed (L/450)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.968 @ 12' 4 1/8"	1.167	Passed (L/289)		1.0 D + 1.0 L (All Spans)

Member Length : 23' 9" System : Floor Member Type : Flush Beam

Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Member should be side-loaded from both sides of the member or braced to prevent rotation.

		Bearing Leng	th	Loads to Supports (lbs)				
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	4.00"	1.50"	1481	3479	470	4960	1 1/2" Rim Board
2 - Stud wall - DF	5.50"	4.00"	1.50"	2268	3802	1439	6198	1 1/2" Rim Board

[•] Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	23' 9" o/c	
Bottom Edge (Lu)	23' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	1 1/2" to 23' 10 1/2"	N/A	30.6			
1 - Uniform (PSF)	0 to 24' (Front)	1' 4"	12.0	40.0	-	Default Load
2 - Point (lb)	16' 10 1/2" (Front)	N/A	802	604	769	Linked from: H1, Support 2
3 - Uniform (PLF)	0 to 24' (Front)	N/A	34.5	213.0	-11.3	Linked from: FJ4, Support 1
4 - Point (lb)	16' 10 1/2" (Front)	N/A	1186	-	1753	Linked from: R5, Support 1
5 - Point (lb)	14' 10 1/2" (Front)	N/A	-179	284	-343	Linked from: B4, Support 1

Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



Page 48 / 67

1 piece(s) 5 1/2" x 14" 24F-V4 DF Glulam



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	7246 @ 4"	13750 (4.00")	Passed (53%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	5712 @ 1' 7 1/2"	13603	Passed (42%)	1.00	1.0 D + 1.0 L (All Spans)
Pos Moment (Ft-lbs)	24176 @ 7' 2 1/2"	35933	Passed (67%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.278 @ 7' 2 1/2"	0.344	Passed (L/594)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.363 @ 7' 2 1/2"	0.688	Passed (L/454)		1.0 D + 1.0 L (All Spans)

Member Length: 14' 2" System: Floor

Member Type : Flush Beam Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Critical positive moment adjusted by a volume/size factor of 1.00 that was calculated using length L = 13' 9".
- The effects of positive or negative camber have not been accounted for when calculating deflection.
- The specified glulam is assumed to have its strong laminations at the bottom of the beam. Install with proper side up as indicated by the manufacturer.
- · Applicable calculations are based on NDS.

Supports	S S S S S S S S S S S S S S S S S S S	Bearing Length		Loads to Supports (lbs)				
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	4.00"	2.11"	1738	5633	-32	7372	1 1/2" Rim Board
2 - Stud wall - DF	5.50"	4.00"	2.11"	1738	5633	-32	7372	1 1/2" Rim Board

[•] Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	14' 2" o/c	
Bottom Edge (Lu)	14' 2" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	1 1/2" to 14' 3 1/2"	N/A	18.7			
1 - Uniform (PLF)	0 to 14' 5" (Front)	N/A	89.3	298.5		Linked from: FJ2, Support 1
2 - Uniform (PLF)	0 to 14' 5" (Front)	N/A	133.5	483.0	-4.5	Linked from: FJ1, Support 2

Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, DJ1

1 piece(s) 2 x 8 DF No.2 @ 16" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	278 @ 5' 10 1/2"	1406 (1.50")	Passed (20%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	206 @ 5' 3 1/4"	1305	Passed (16%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	363 @ 3' 1 1/2"	1360	Passed (27%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.023 @ 3' 1 1/2"	0.138	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.027 @ 3' 1 1/2"	0.275	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)
TJ-Pro™ Rating	N/A	N/A	N/A		N/A

Member Length: 5' 9 1/4" System: Floor Member Type: Joist Building Use: Residential

Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.
- No composite action between deck and joist was considered in analysis.

Supports	Bearing Length		Loads to Supports (lbs)					
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	4.25"	1.50"	50	250	104	316	1 1/4" Rim Board
2 - Hanger on 7 1/4" DF beam	1.50"	Hanger ¹	1.50"	46	230	96	290	See note 1

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- ¹ See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' 9" o/c	
Bottom Edge (Lu)	5' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie									
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories			
2 - Face Mount Hanger	LU26	1.50"	N/A	6-10dx1.5	4-10dx1.5				

Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 6'	16"	12.0	60.0	25.0	Default Load

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

File Name: McReynolds PC

FLOOR, DJ2

1 piece(s) 2 x 8 DF No.2 @ 16" OC

Overall Length: 10'



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	480 @ 9' 10 1/2"	1406 (1.50")	Passed (34%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	398 @ 9' 3 1/4"	1305	Passed (30%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	1083 @ 5' 1 1/2"	1360	Passed (80%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.204 @ 5' 1 1/2"	0.237	Passed (L/558)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.243 @ 5' 1 1/2"	0.475	Passed (L/469)		1.0 D + 0.75 L + 0.75 S (All Spans)
TJ-Pro™ Rating	N/A	N/A	N/A		N/A

Member Length: 9' 9 1/4" System: Floor Member Type : Joist Building Use: Residential

Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/480) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.
- No composite action between deck and joist was considered in analysis.

	Bearing Length		Loads to Supports (lbs)					
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	4.25"	1.50"	82	410	171	518	1 1/4" Rim Board
2 - Hanger on 7 1/4" DF beam	1.50"	Hanger ¹	1.50"	78	390	163	492	See note 1

- Rim Board is assumed to carry all loads applied directly above it, bypassing the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- 1 See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	8' 3" o/c	
Bottom Edge (Lu)	9' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie								
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories		
2 - Face Mount Hanger	LU26	1.50"	N/A	6-10dx1.5	4-10dx1.5			

[·] Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 10'	16"	12.0	60.0	25.0	Default Load

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/ document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 6 x 10 DF No.2

Overall Length: 13' 2 1/4"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1619 @ 13' 1"	9453 (2.75")	Passed (17%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	1300 @ 1' 3"	5922	Passed (22%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	4841 @ 6' 8 1/2"	6032	Passed (80%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.232 @ 6' 8 1/2"	0.425	Passed (L/660)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.291 @ 6' 8 1/2"	0.637	Passed (L/526)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length: 13' 2 1/4"

System: Floor

Member Type : Drop Beam Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

Supports	Barrier B	Bearing Length			Loads to Sup			
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.50"	340	1258	523	1676	Blocking
2 - Stud wall - DF	2.75"	2.75"	1.50"	329	1215	505	1619	Blocking

[·] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	13' 2" o/c	
Bottom Edge (Lu)	13' 2" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 13' 2 1/4"	N/A	13.2			
1 - Uniform (PLF)	0 to 13' 2 1/4" (Front)	N/A	37.5	187.5	78.0	Linked from: DJ1 Support 1

[•] Side loads are assumed to not induce cross-grain tension.


Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumwent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



1 piece(s) 6 x 10 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2100 @ 2"	12031 (3.50")	Passed (17%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	1585 @ 1' 1"	5922	Passed (27%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	4898 @ 5' 2 3/4"	6032	Passed (81%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.151 @ 5' 2 3/4"	0.338	Passed (L/803)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.186 @ 5' 2 3/4"	0.506	Passed (L/654)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length: 10' 5 1/2"

System: Floor

Member Type : Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

		Bearing Length			Loads to Sup			
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	3.50"	3.50"	1.50"	391	1608	671	2100	Blocking
2 - Stud wall - DF	3.50"	3.50"	1.50"	391	1608	671	2100	Blocking

Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	10' 6" o/c	
Bottom Edge (Lu)	10' 6" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 10' 5 1/2"	N/A	13.2			
1 - Uniform (PLF)	0 to 10' 5 1/2" (Front)	N/A	61.5	307.5	128.3	Linked from: DJ2, Support 1

[·] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, H7 (Steel)

1 piece(s) W10X26 (A992) ASTM Steel



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	7036 @ 18' 7 1/2"	10819 (3.00")	Passed (65%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	6905 @ 18' 6"	53560	Passed (13%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	33963 @ 11' 6 3/8"	36389	Passed (93%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.250 @ 9' 7 1/2"	0.617	Passed (L/888)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.485 @ 9' 7 7/16"	0.925	Passed (L/458)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 18' 9" System : Floor Member Type : Drop Beam

2

Building Use: Residential
Building Code: IBC 2018
Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- · Applicable calculations are based on ANSI/AISC 360-16.
- $\bullet\,$ A lateral-torsional buckling factor (Cb) of 1.0 has been assumed.

1

		Bearing Length			Loads to Sup			
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Stud wall - DF	3.00"	3.00"	3.00"	2929	2891	1230	6021	Blocking
2 - Stud wall - DF	3.00"	3.00"	3.00"	3411	3013	1820	7036	Blocking

• Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	End Bearing Points	
Bottom Edge (Lu)	End Bearing Points	

Vertical Loads	Location (Side)	Tributary Width	Dead (0,90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 18' 9"	N/A	26.0			
1 - Uniform (PLF)	0 to 18' 9" (Front)	N/A	229.5	294.0	61.5	Linked from: FJ4, Support 2
2 - Point (lb)	12' 3" (Front)	N/A	1550	392	1897	Linked from: B4, Support 2

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, H8

1 piece(s) 6 x 10 DF No.2

Overall Length: 9'6"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1779 @ 0	5156 (1.50")	Passed (35%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	1436 @ 11"	5922	Passed (24%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	4226 @ 4' 9"	6032	Passed (70%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.081 @ 4' 9"	0.317	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.134 @ 4' 9"	0.475	Passed (L/848)		1.0 D + 1.0 L (All Spans)

Member Length : 9' 6" System : Wall Member Type : Header Building Use : Residentia

Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

		Bearing Length			Loads to Sup			
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	707	1073	342	1779	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	707	1073	342	1779	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	9' 6" o/c	
Bottom Edge (Lu)	9' 6" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 9' 6"	N/A	13.2			
1 - Uniform (PSF)	0 to 9' 6"	1' 4"	12.0	40.0	12	Default Load
2 - Uniform (PLF)	0 to 9' 6"	N/A	85.0	345	-	
3 - Uniform (PLF)	0 to 9' 6"	N/A	34.5	172.5	72.0	Linked from: DJ1, Support 2

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




MEMBER REPORT PASSED

FLOOR, H9

1 piece(s) 6 x 10 DF No.2

Overall Length: 6' 6"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1702 @ 0	5156 (1.50")	Passed (33%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	1210 @ 11"	5922	Passed (20%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	2739 @ 3' 3"	6032	Passed (45%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.028 @ 3' 3"	0.217	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.041 @ 3' 3"	0.325	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 6' 6" System : Wall Member Type : Header Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

		Bearing Length			Loads to Sup			
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	561	1124	397	1702	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	561	1124	397	1702	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 6" o/c	
Bottom Edge (Lu)	6' 6" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 6' 6"	N/A	13.2			
1 - Uniform (PSF)	0 to 6' 6"	1' 4"	12.0	40.0	-	Default Load
2 - Uniform (PLF)	0 to 6' 6"	N/A	85.0	-	-	
3 - Uniform (PLF)	0 to 6' 6"	N/A	58.5	292.5	122.3	Linked from: DJ2, Support 2

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




11/5/2024 9:39:46 PM UTC ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3 File Name: McReynolds PC

Page 56 / 67

FLOOR, H10

1 piece(s) 6 x 10 DF No.2





Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	901 @ 0	5156 (1.50")	Passed (17%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	747 @ 11"	5922	Passed (13%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	2421 @ 5' 4 1/2"	6032	Passed (40%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.031 @ 5' 4 1/2"	0.358	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.099 @ 5' 4 1/2"	0.538	Passed (L/999+)		1.0 D + 1.0 L (All Spans)

Member Length : 10' 9" System : Wall Member Type : Header Building Use : Residential Building Code : IBC 2018

Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

		Bearing Length		Loa	ds to Supports		
Supports	Total	Available	Required	Dead	Floor Live Factored Accesso	Accessories	
1 - Trimmer - DF	1.50"	1.50"	1.50"	614	287	901	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	614	287	901	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	10' 9" o/c	
Bottom Edge (Lu)	10' 9" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Floor Live (1.00)	Comments
0 - Self Weight (PLF)	0 to 10' 9"	N/A	13.2		
1 - Uniform (PSF)	0 to 10' 9"	1' 4"	12.0	40.0	Default Load
2 - Uniform (PLF)	0 to 10' 9"	N/A	85.0	-	

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, H11 1 piece(s) 6 x 10 DF No.2

NAC 41



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	5770 @ 1 1/2"	10313 (3.00")	Passed (56%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	3833 @ 1' 1/2"	6810	Passed (56%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	5920 @ 2' 11 13/16"	6937	Passed (85%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.046 @ 3' 2 3/16"	0.208	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.083 @ 3' 2 1/8"	0.313	Passed (L/902)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 6' 6" System : Wall Member Type : Header Building Use : Residential Building Code : IBC 2018

Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

Supports	Bearing Length			Loads to Supports (lbs)				
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Trimmer - DF	3.00"	3.00"	1.68"	2658	2216	1934	5770	None
2 - Trimmer - DF	3.00"	3.00"	1.50"	1621	1448	1222	3623	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	6' 6" o/c	
Bottom Edge (Lu)	6' 6" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 6' 6"	N/A	13.2			
1 - Uniform (PSF)	0 to 9"	11' 9"	12.0	40.0	-	
2 - Uniform (PLF)	9" to 6' 6"	N/A	185.3	417.0	72.0	Linked from: FJ3, Support 1
3 - Uniform (PLF)	0 to 6' 6"	N/A	85.0	-	-	
4 - Uniform (PLF)	0 to 6' 6"	N/A	174.5	-	275.5	Linked from: RJ3, Support 1
5 - Point (lb)	9"	N/A	1335	914	951	Linked from: B2, Support 1

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



FLOOR, H12

1 piece(s) 4 x 10 DF No.2

Overall Length: 5' 3"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2266 @ 0	3281 (1.50")	Passed (69%)		1.0 D + 1.0 L (All Spans)
Shear (lbs)	1493 @ 10 3/4"	3885	Passed (38%)	1.00	1.0 D + 1.0 L (All Spans)
Moment (Ft-lbs)	2974 @ 2' 7 1/2"	4492	Passed (66%)	1.00	1.0 D + 1.0 L (All Spans)
Live Load Defl. (in)	0.026 @ 2' 7 1/2"	0.175	Passed (L/999+)		1.0 D + 1.0 L (All Spans)
Total Load Defl. (in)	0.040 @ 2' 7 1/2"	0.262	Passed (L/999+)		1.0 D + 1.0 L (All Spans)

Member Length: 5' 3" System: Wall Member Type: Header Building Use: Residential Building Code: IBC 2018

Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- · Applicable calculations are based on NDS.

Supports		Bearing Length			Loads to Sup			
	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
L - Trimmer - DF	1.50"	1.50"	1.50"	793	1473	144	2266	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	793	1473	144	2266	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	5' 3" o/c	
Bottom Edge (Lu)	5' 3" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 5' 3"	N/A	8.2			
1 - Uniform (PLF)	0 to 5' 3"	N/A	294.0	561.0	54.8	Linked from: FJ1 Support 1

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


ForteWEB Software Operator	Job Notes		
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com			



FLOOR, H13

1 piece(s) 4 x 10 DF No.2

Overall Length: 4' 3"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	1613 @ 0	3281 (1.50")	Passed (49%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Shear (lbs)	933 @ 10 3/4"	4468	Passed (21%)	1.15	1.0 D + 0.75 L + 0.75 S (All Spans)
Moment (Ft-lbs)	1713 @ 2' 1 1/2"	5166	Passed (33%)		1.0 D + 0.75 L + 0.75 S (All Spans)
Live Load Defl. (in)	0.008 @ 2' 1 1/2"	0.142	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)
Total Load Defl. (in)	0.015 @ 2' 1 1/2"	0.213	Passed (L/999+)		1.0 D + 0.75 L + 0.75 S (All Spans)

Member Length : 4' 3" System : Wall Member Type : Header Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)				
Supports	Total	Available	Required	Dead	Floor Live	Snow	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	726	634	547	1613	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	726	634	547	1613	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	4' 3" o/c	
Bottom Edge (Lu)	4' 3" o/c	

Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location	Tributary Width	Dead (0.90)	Floor Live (1.00)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 4' 3"	N/A	8.2			
1 - Uniform (PLF)	0 to 4' 3"	N/A	89.3	298.5	3	Linked from: FJ2, Support 2
2 - Uniform (PLF)	0 to 4' 3"	N/A	85.0	-	-	
3 - Uniform (PLF)	0 to 4' 3"	N/A	159.4	-	257.5	Linked from: RJ1, Support 1

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




MEMBER REPORT

FLOOR, RIM JOIST AT STAIRS

1 piece(s) 3 1/2" x 14" 1.55E TimberStrand® LSL

Overall Length: 8' 11 1/16"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	68 @ 0	4069 (1.50")	Passed (2%)		1.0 D (All Spans)
Shear (lbs)	49 @ 1' 3 1/2"	9114	Passed (1%)	0.90	1.0 D (All Spans)
Moment (Ft-lbs)	152 @ 4' 5 1/2"	19656	Passed (1%)	0.90	1.0 D (All Spans)
Vert Live Load Defl. (in)	0.000 @ 0	0.297	Passed (2L/999+)		1.0 D (All Spans)
Vert Total Load Defl. (in)	0.002 @ 4' 5 1/2"	0.446	Passed (L/999+)		1.0 D (All Spans)
Lat Member Reaction (lbs)	1445 @ 8' 11 1/16"	N/A	Passed (N/A)	1.60	1.0 D + 0.6 W
Lat Shear (lbs)	1310 @ 5"	7840	Passed (17%)	1.60	1.0 D + 0.6 W
Lat Moment (Ft-lbs)	3222 @ mid-span	9966	Passed (32%)	1.60	1.0 D + 0.6 W
Lat Deflection (in)	0.424 @ mid-span	0.446	Passed (L/253)		1.0 D + 0.6 W
Bi-Axial Bending	0.33	1.00	Passed (33%)	1.60	1.0 D + 0.6 W

Member Length: 8' 11 1/16"

System: Wall Member Type: Header Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

- Deflection criteria: LL (L/360) and TL (L/240).
- Lateral deflection criteria: Wind (L/240)

Supports	E	Loads to				
	Total	Available	Required	Dead	Factored	Accessories
1 - Trimmer - DF	1.50"	1.50"	1.50"	68	68	None
2 - Trimmer - DF	1.50"	1.50"	1.50"	68	68	None

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	8' 11" o/c	
Bottom Edge (Lu)	8' 11" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Lateral Connections								
Supports	Stud Size	Stud Material	Connector	Type/Model	Quantity	Nailing		
Left	2X	Douglas Fir-Larch		N/A	N/A	N/A		
Right	2X	Douglas Fir-Larch		N/A	N/A	N/A		

Vertical Load	Location	Tributary Width	Dead (0.90)	Comments
0 - Self Weight (PLF)	0 to 8' 11 1/16"	N/A	15.3	

			Wind	
Lateral Load	Location	Tributary Width	(1.60)	Comments
1 - Uniform (PSF)	Full Length	9'	60.0	

[•] IBC Table 1604.3, footnote f: Deflection checks are performed using 42% of this lateral wind load.


ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



Low Roof, LRJ1

1 piece(s) 2 x 10 DF No.2 @ 24" OC

Overall Length: 13' 1"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)	
Member Reaction (lbs)	389 @ 12' 11 1/2"	1406 (1.50")	Passed (28%)		1.0 D + 1.0 S (Alt Spans)	
Shear (lbs)	358 @ 3' 8 3/4"	1915	Passed (19%)	1.15	1.0 D + 1.0 S (All Spans)	
Moment (Ft-lbs)	947 @ 8' 1 1/8"	2334	Passed (41%)	1.15	1.0 D + 1.0 S (Alt Spans)	
Live Load Defl. (in)	0.071 @ 7' 10 15/16"	0.512	Passed (L/999+)		1.0 D + 1.0 S (Alt Spans)	
Total Load Defl. (in)	0.110 @ 7' 11 1/4"	0.682	Passed (L/999+)		1.0 D + 1.0 S (Alt Spans)	

Member Length: 12' 11 1/2"

System: Roof
Member Type: Joist
Building Use: Residential
Building Code: IBC 2018
Design Methodology: ASD
Member Pitch: 0.25/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Beveled Plate - DF	5.50"	5.50"	1.50"	246	410	657	Blocking
2 - Hanger on 9 1/4" DF beam	1.50"	Hanger ¹	1.50"	146	253	399	See note 1

- . Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.
- At hanger supports, the Total Bearing dimension is equal to the width of the material that is supporting the hanger
- 1 See Connector grid below for additional information and/or requirements.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	13' o/c	
Bottom Edge (Lu)	13' o/c	

[•]Maximum allowable bracing intervals based on applied load.

Connector: Simpson Strong-Tie								
Support	Model	Seat Length	Top Fasteners	Face Fasteners	Member Fasteners	Accessories		
2 - Face Mount Hanger	LRU28Z	1.94"	N/A	6-10dx1.5	5-10d			

[·] Refer to manufacturer notes and instructions for proper installation and use of all connectors.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 13' 1"	24"	15.0	25.0	Default Load

Weyerhaeuser Notes


Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



Low Roof, LRJ2

1 piece(s) 2 x 10 DF No.2 @ 24" OC



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	591 @ 10' 7 1/4"	3282 (3.50")	Passed (18%)		1.0 D + 1.0 S (Adj Spans)
Shear (lbs)	325 @ 9' 8 1/4"	1915	Passed (17%)	1.15	1.0 D + 1.0 S (Adj Spans)
Moment (Ft-lbs)	799 @ 5' 8 9/16"	2334	Passed (34%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.052 @ 5' 10"	0.473	Passed (L/999+)		1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.079 @ 5' 9 3/4"	0.631	Passed (L/999+)		1.0 D + 1.0 S (Alt Spans)

Member Length : 13' System : Roof Member Type : Joist Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD Member Pitch : 0.25/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.

Supports	B Comment	Bearing Length			to Suppor		
	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Beam - DF	3,50"	3.50"	1.50"	169	290	459	Blocking
2 - Beam - DF	3.50"	3.50"	1.50"	221	370	591	Blocking

[•] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	13' o/c	
Bottom Edge (Lu)	13' o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 13'	24"	15.0	25.0	Default Load

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.


ForteWEB Software Operator	Job Notes			
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com				



Low Roof, LRJ3

1 piece(s) 2 x 12 DF No.2 @ 24" OC

Sloped Length: 15' 5 9/16"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	616 @ 2' 7 3/4"	3382 (3.50")	Passed (18%)		1.0 D + 1.0 S (Adj Spans)
Shear (lbs)	316 @ 3' 8 7/16"	2329	Passed (14%)	1.15	1.0 D + 1.0 S (Adj Spans)
Moment (Ft-lbs)	758 @ 7' 6"	3138	Passed (24%)	1.15	1.0 D + 1.0 S (Alt Spans)
Live Load Defl. (in)	0.031 @ 7' 6"	0.500	Passed (L/999+)		1.0 D + 1.0 S (Alt Spans)
Total Load Defl. (in)	0.045 @ 7' 6"	0.667	Passed (L/999+)		1.0 D + 1.0 S (Alt Spans)

Member Length: 15' 8 3/8"

System: Roof Member Type: Joist Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD Member Pitch: 3/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Overhang deflection criteria: LL (2L/240) and TL (2L/180).
- · Allowed moment does not reflect the adjustment for the beam stability factor.
- A 15% increase in the moment capacity has been added to account for repetitive member usage.
- · Applicable calculations are based on NDS.

		Bearing Length			to Suppor		
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Beveled Plate - DF	3.50"	3.50"	1.50"	232	384	616	Blocking
2 - Beveled Plate - DF	3.50"	3.50"	1.50"	232	384	616	Blocking

· Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	15' 6" o/c	
Bottom Edge (Lu)	15' 6" o/c	

[•]Maximum allowable bracing intervals based on applied load.

•Dimensions for lateral bracing intervals are measured along the length of the member for sloped conditions.

Vertical Load	Location (Side)	Spacing	Dead (0.90)	Snow (1.15)	Comments
1 - Uniform (PSF)	0 to 15'	24"	15.0	25.0	Default Load

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



11/5/2024 9:39:46 PM UTC

ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3


File Name: McReynolds PC



MEMBER REPORT

Low Roof, LRB1

1 piece(s) 6 x 12 DF No.2



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2587 @ 4"	18906 (5.50")	Passed (14%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	2100 @ 1' 5"	8244	Passed (25%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	8886 @ 7' 6 1/4"	10166	Passed (87%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.217 @ 7' 6 1/4"	0.719	Passed (L/794)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.365 @ 7' 6 1/4"	0.958	Passed (L/473)		1.0 D + 1.0 S (All Spans)

Member Length: 15' 1/2"

System: Roof

Member Type: Drop Beam Building Use: Residential Building Code: IBC 2018 Design Methodology: ASD

Member Pitch: 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- · Applicable calculations are based on NDS.

	Bearing Length			Loads to Supports (lbs)			
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.50"	1046	1542	2587	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	1046	1542	2587	Blocking

· Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	15' 1" o/c	
Bottom Edge (Lu)	15' 1" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 15' 1/2"	N/A	16.0		
1 - Uniform (PLF)	0 to 15' 1/2" (Front)	N/A	123.0	205.0	Linked from: LRJ1, Support 1

Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

The product application, input design loads, dimensions and support information have been provided by ForteWEB Software Operator

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		




ForteWEB v3.8, Engine: V8.4.1.24, Data: V8.1.6.3

Low Roof, LRB2

1 piece(s) 6 x 10 DF No.2

Overall Length: 8' 5"



Drawing is Conceptual. All locations are measured from the outside face of left support (or left cantilever end). All dimensions are horizontal (typ.).

Design Results	Actual @ Location	Allowed	Result	LDF	Load: Combination (Pattern)
Member Reaction (lbs)	2543 @ 4"	18906 (5.50")	Passed (13%)		1.0 D + 1.0 S (All Spans)
Shear (lbs)	1788 @ 1' 3"	6810	Passed (26%)	1.15	1.0 D + 1.0 S (All Spans)
Moment (Ft-lbs)	4536 @ 4' 2 1/2"	6937	Passed (65%)	1.15	1.0 D + 1.0 S (All Spans)
Live Load Defl. (in)	0.059 @ 4' 2 1/2"	0.387	Passed (L/999+)		1.0 D + 1.0 S (All Spans)
Total Load Defl. (in)	0.096 @ 4' 2 1/2"	0.517	Passed (L/969)		1.0 D + 1.0 S (All Spans)

Member Length: 8' 5" System: Roof

Member Type : Drop Beam Building Use : Residential Building Code : IBC 2018 Design Methodology : ASD Member Pitch : 0/12

- Deflection criteria: LL (L/240) and TL (L/180).
- Allowed moment does not reflect the adjustment for the beam stability factor.
- Lumber grading provisions must be extended over the length of the member per NDS 4.2.5.5.
- Applicable calculations are based on NDS.

		Bearing Length			to Suppor		
Supports	Total	Available	Required	Dead	Snow	Factored	Accessories
1 - Stud wall - DF	5.50"	5.50"	1.50"	986	1557	2543	Blocking
2 - Stud wall - DF	5.50"	5.50"	1.50"	986	1557	2543	Blocking

[•] Blocking Panels are assumed to carry no loads applied directly above them and the full load is applied to the member being designed.

Lateral Bracing	Bracing Intervals	Comments
Top Edge (Lu)	8' 5" o/c	
Bottom Edge (Lu)	8' 5" o/c	

[•]Maximum allowable bracing intervals based on applied load.

Vertical Loads	Location (Side)	Tributary Width	Dead (0.90)	Snow (1.15)	Comments
0 - Self Weight (PLF)	0 to 8' 5"	N/A	13.2		
1 - Uniform (PLF)	0 to 8' 5" (Front)	N/A	110.5	185.0	Linked from: LRJ2, Support 2
2 - Uniform (PLF)	0 to 8' 5" (Front)	N/A	110.5	185.0	Linked from: LRJ2, Support 2

[•] Side loads are assumed to not induce cross-grain tension.

Weyerhaeuser Notes

Weyerhaeuser warrants that the sizing of its products will be in accordance with Weyerhaeuser product design criteria and published design values. Weyerhaeuser expressly disclaims any other warranties related to the software. Use of this software is not intended to circumvent the need for a design professional as determined by the authority having jurisdiction. The designer of record, builder or framer is responsible to assure that this calculation is compatible with the overall project. Accessories (Rim Board, Blocking Panels and Squash Blocks) are not designed by this software. Products manufactured at Weyerhaeuser facilities are third-party certified to sustainable forestry standards. Weyerhaeuser Engineered Lumber Products have been evaluated by ICC-ES under evaluation reports ESR-1153 and ESR-1387 and/or tested in accordance with applicable ASTM standards. For current code evaluation reports, Weyerhaeuser product literature and installation details refer to www.weyerhaeuser.com/woodproducts/document-library.

ForteWEB Software Operator	Job Notes	
Matt Nava Nava Contracting and Engineering (503) 238-0633 Mattsnava@gmail.com		



Mali McReynolds Pacific City, Oregon M.V.Nava 11/05/24

SUMMARY

		P(seismic)	P(wind)	P(wind) 9.6 psf	v(seismic)	v(wind)	Length	No.	
1	Upper Rup1	2566	2127	749	253 1843	210 1437	10.1	1	C/2
	Main Rup1 Rup2 Rup3	9	5354	1757	120 652 890 963	160 568 880 977	17.6 9.3 6.7	1 1 1	S/0
2	Upper Rup1 Rup2 Rup3	<u>)</u>	4879	1886	172 1208 1237 1302	230 1612 1650 1736	9.3 7.8 4.2	1 1 1	S/6 or S/2
	Main Rup1 Rup2		7866	3041	214 1669 1826	308 2338 2544	15.5 10.0	1	C/8
3	Upper Rup1 Rup2		1745	600	76 310 497	78 237 483	16.3 6.0	1	S/0
	Main Rup1 Rup2		3355	1107	89 386 411	109 346 378	15.9 15.0	1 1	S/0

SUMMARY CONTINUED

Α	P(seismic)	P(wind)	P(wind) 9.6 psf	v(seismic)	v(wind)	Length	No.	
Upper Rup	2277 1	1656	1032	569 4535	414 3288	1.0	4	WSWH18x
Main Rup	3284 1	5279	2271	821 12313	1320 15798	1.0	4	WSWH18x
В								
Upper Rup	3607 1	2632	1851	424 3240	310 2273	8.5	1	D/3
Main Rup	5395 1	8242	4020	635 9085	970 11243	8.5	1	E/10
С								
Upper Rup Rup		1167	818	116 821 875	97 634 706	6.0 3.0	1 2	S/0
Main Rup	2529 1	3991	1748	440 6005	694 8066	2.9	2	D/8

Client: Project:	Mali McReyno Pacific City, C								By: Date:	M.V.Nava 11/05/24	
Seismic Si Importance Seismic Us	e Factor se Group pectral Respon Ss S1 Sds =	nse Coeffi 1.279 0.667 1.028	II D 1.00 I cients Per section Per section		.2.3	F: F	Roof Seism a = 1 v = 1	.2 .5	Load dtl Snow Lo Per Tble 1	oad 613.2.3(1) 613.2.3(2)	15 25 0
Analysis P	Sdl = rocedure Used	0.670 I	ASCE 7 -				s = 0.456				
1a and 1b 2 3 4 5 Lt Framed 25 % INCF Load Direct Front to Ba Basic Seis	Horizontal Irro Torsional for Reentrant Co Diaphragm D Out of Plane Nonparallel S Construction E REASE IN SEIS ction: ack (Building Co mic force resis	egularity non-flexis orners viscontinu Offset System Building D SMIC DIA Grids 1 - 5 ting syste	oes Not Exc PHRAGM C	ok ok ok ok seed five sto	ories in he R FORCE	2 3 4 5 ight excluding S REQUIRED Respons Modification F R	Vertice Vertice Weigh Geom In-Pla Weak D BY SEC	cal Irregatory Story Int netrical ane Dis k Story ent CTION	12.3.3.4 Seismic Overstreng Omega	gth	ok ok ok ok ok ok ok ok d Amplification Cd
	V = <u>\$</u>	<u>Sds * W =</u> R	-	0.158	W	Front - to	- Back L	Load D	irection		
	<u>ction:</u> Side (Building mic force resis				ı	Respons Modification F R			Seismic Overstrenç Omega	gth	Deflection Amplication Cd
A. 15. Ligh	it-frame (wood)) walls sh	eathed w/wo	od structura	al x	6.5			3		4
	V = <u>S</u>	<u>Sds * W =</u> R	<u>:</u> _	0.158	W	Front - to	o - Back L	Load D	irection		

Mali McReynolds

Pacific City, Oregon

By: Date: M.V.Nava 11/05/24

Basic Wind Speed 3 Sec Gust

mph

Wind Exposure

135 D

Importance Factor Per IBC Table 1604.5 1.00 Building Category per IBC Table 1604.5 II

Front - to - Back Slope:

4:12

Roof Angle

18.4

7

Degrees

Left - to - Right Slope

4:12

Roof Angle

18.4

Degrees

Roof Height

23.875 23.875

Eave Height

17.5 17.5

Roof Mean Height

20.7

Least Building Dimension

38.5 ft

Analysis Procedure Used

ASCE 7 - 10, Envelope Procedure Ch. 28

Load Combinations: 0.6D+(0.7E OR 0.6W)

Mean Roof Height does not exceed least horiz dimension ok Mean Roof Height does not exceed 60 ft/Exp B or 30ft/Exp C ok Building is not located on upper half of isolated hill or escarpment ok Building is regular in shape and approximately symmetrical ok Roof Slope is less than 12:12 ok

Height and Exposure Adjustment Coefficient per Figure 28.6-1 (λ)

1.55

<u>B</u>	<u>C</u>	<u>D</u>
1	1.21	1.47
1	1.29	1.55
1	1.35	1.61
1	1.4	1.66
1.05	1.45	1.7
1.09	1.49	1.74
1.12	1.53	1.78
	1 1 1 1 1 1.05 1.09	1 1.21 1 1.29 1 1.35 1 1.4 1.05 1.45 1.09 1.49

Simplified Design Wind Pressure:

			Zone		
Front - to - Back Direction: angle =	4:12	Α	В	С	D
	Ps30 =	40.1	-10.5	26.7	-5.9
Ps = (λ) *(Importance Factor)*0.6*(Ps30)					
Ps =Design	Wind Pressure =	37.25	-9.77	24.83	-5.44
Left - to - Right Direction: angle	4:12				
	Ps30 =	40.05	-10.50	26.7	-5.85
Ps = (λ) *(Importance Factor)*0.6*(Ps30)					
Ps =Design	Wind Pressure =	37.25	-9.77	24.83	-5.44
Building Zone Dimension a:					
10 %	least Building Dime	nsion	3.85		
.04 %	least Building Dime	ension	1.54		

.4h =a = 3.85

Client: Project:	Mali McRey Pacific City	, Oregon	405
Wind		Wind Speed	
Zone A	Zone B	Zone C	Zone D
37.2465	-9.765	24.831	-5.4405
	3.85		3.85
Lines :	1	2	3
Eave Ht	17.5	17.5	17.5
Wall Trib	10.125	19.25	9.125
L(tot)	10.125	21.257	22.25
Upper	9.5	9.5	9.5
Wall Trib	12	19.25	7.25
L(tot)	33.503	25.5	30.875
Main	5	5	5

By: M.V.Nava Date: 11/05/24

Exposure D

Building Dimension a =

Building Dimension a

3.85

	Loads er Roof in Roof Upper	930 1252	2967	647
P		2127	4879	1745
V		210	230	78
	Rup1	1437	1612	237
	Rup2	1680	1650	483
	Rup2	1680	1736	627
Main				
Р		5354	7866	3355
V		160	308	109
	Rup1	568	2338	346
	Rup2	880	2544	378
	Rup3	977	2919	941
Base	Р	7333	9291	5187

TOTAL BASE WIND 21811 lb

Client: Project: Wind	Mali McRey Pacific City Basic V		3.85	By: M.V.Nava Date: 11/05/24 Exposure 3	
Zone A	Zone B	Zone C	Zone D	Building Dimension a =	3.85
16	8	16	8	27.1.5 Minimum Design Wind Loads	
9.6	4.8	9.6	4.8	Ps=0.6*Ps30	
	3.85	0	3.85		
Lines : Eave Ht	1 17.5	2 17.5	3 17.5		
Wall Trik		19.25	9.125		
L(tot	,	21.257	22.25		
Upper	9.5	9.5	9.5		
Wall Trik L(tot Main		19.25 25.5 5	7.25 30.875 5		

Roof Loads			
Upper Roof	360	1147	250
Main Roof	360		
Upper			
P	749	1886	600
V	74	89	27
Rup1	349	486	-174
Rup2	592	524	72
Rup2	592	610	216
Main			
Р	1757	3041	1107
V	52	119	36
Rup1	-245	547	-278
Rup2	68	753	-246
Rup3	165	1128	317
Base P	2963	3959	2219

TOTAL BASE WIND 9141 lb

Client: Project:	Mali McReyn Pacific City, 0			By: Date:	M.\	/.Nava 11/05/24	
Wind Zone A 37.2465	Basic Wind S Zone B -9.765 3.85	Speed = Zone C 24.831	135.00 Zone D -5.4405 3.85	Exposure	D	Building dimension a	3.85
Lines:	Α	В	С				
Eave Ht	17.5	17.5	17.5				
Wall Trib L(tot		26.5 8.5	11.75 12				
Upper	9.5	9.5	9.5				
Wall Trib	14.75	25.25	10.5				
L(tot) 4	8.5	5.75				
Main	0	0	0				

Roof Load				
Upper Ro	oof	0	0	0
Unner				
Upper				
Р		1656	2632	1167
V		414	310	97
Ru	.p1 3	3288	2273	634
Ru	.p2	3312	2477	706
Ru	.p3 3	3312	2477	778
Main				
Р		5279	8242	3991
V		1320	970	694
Ru	up1 1	5798	11243	8066
		5851	11689	8217
Ru	.p3 1	5851	11689	8217
Base P		5978	9245	4896

M.V.Nava Client: Mali McReynolds By: 11/05/24 Project: Pacific City, Oregon Date: D 135.00 Exposure Basic Wind Speed = Wind Zone C Zone D Zone A Zone B 27.1.5 Minimum Design Wind Loads 16 8 16 8 Ps=0.6*Ps30 9.6 4.8 9.6 4.8 3.85 0 3.85 Building dimension a 3.85 С Lines: Α В Eave Ht 17.5 17.5 17.5 Wall Trib 14.75 26.5 11.75 12 8.5 L(tot) 4 9.5 Upper 9.5 9.5 25.25 10.5 Wall Trib 14.75 8.5 5.75 L(tot) 4 0 0 0 Main

	of Loads per Roof	466	833	367
	Р			
	Р	1032	1851	818
	V	258	218	68
	Rup1	2041	1538	401
	Rup2	2065	1742	473
	Rup3	2065	1742	545
F	,			
	P	2271	4020	1748
	V	568	473	304
	Rup1	7407	5788	3876
	Rup2	7459	6234	4027
	Rup3	7459	6234	4027
Bas	se P	2575	4666	2185

TOTAL BASE WIND 9426

lb

Mali McReynolds Pacific City, Oregon

By: Date:

M.V.Nava 11/05/24

Line 1

Seismic (Seismic Calculations A. 15. Light-frame (wood) walls sheathed w/wood structural panels rated for shear resistance									
V =	(Sds)Wt/R	1	Sds =	1.028316	R=	6.5				
V =	50									
		A residence of the second of t		<u>wxhx</u>						
<u>Lvl</u>	Ht.	Wt.	wxhx	Totwxhx	<u>Fx</u>	V (total)	V(design)			
Eave	17.5	13,185	230733.56	0.623856	2,819					
Upper	9.5	13,823	131320.88	0.3550646	1,605	2,819	2,566			
Main	5	1,559	7796.25	0.0210795	95	4,424	4,026			
						4.540	4.440			
Base		28,567	369850.69	1	4,519	4,519	4,113			
T	00.50	711								
Tot Wt =	28,56 4,51									
V(base) =	4,51	9108								
Q=p x .7E =	13 v 7 F :	= 91 x F								
Design V =	0.91	E								
200.g., v										
LvI	L (tot)	v (Design)								
Upper	10.13	253								
Main	33.50	120								
Lipliff:										
Uplift:	L (tot)	L1	Rup.1	L2	Rup,2	L3	Rup,3			
Uplift: Upper	L(tot) 10.13	L1 10.13	Rup,1 1843	L2 0	Rup,2 2027	L3 0.0	Rup,3 2027			

Mali McReynolds Pacific City, Oregon By: Date: M.V.Nava 11/05/24

Line 2

Seismic	Calculations			frame (wood) ear resistance		eathed w/wo	od structural pane	els
V = V =	(Sds)Wt/R 0.1582	(Wt)	Sds =		R	= 6.5		
		()		<u>wxhx</u>				
<u>Lvl</u>	Ht.	Wt.		Totwxhx	<u>Fx</u>	V (total)	V(design)	
Eave	17.5	19,320		0.6596152	4,024			
Upper	9.5	17,390		0.3223101	1,966	4,024	3,662	
Main	5	1,853		0.0180747	110	5,990	5,451	
IVIAIII	3	1,055	3204.313	0.0100747	110	0,000	-1	
Base		38,562	512561.63	1	6,101	6,101	5552	
base		36,302	312301.03		0,101	0,101	0002	
Tot \\// -	20 562	lho						
Tot Wt =	38,562							
V(base) =	6,101	ibs						
. 75	4075-	04 =						
Q=p x .7E =								
Design V =	0.91	E						
		(D - :)						
LvI		v (Design)						
Upper	21.26	172						
Main	25.50	214						
Uplift:								
Opint.	L (tot used)	L1	Rup,1	L2	Rup,2	L3	Rup,3	
Llanar	L(tot,used)		1208	7.75	1237	4.2	1302	
Upper	21.26	9.34	Section and the section of the secti	10	1826	0.0	2111	
Main	25.50	15.50	1669	10	1020	0.0	2111	

. . . Client:

Project:

Mali McReynolds Pacific City, Oregon

By: Date:

M.V.Nava 11/05/24

Line 3

Seismic	Calculations			frame (wood) ear resistance		eathed w/wo	od structural pan	els
\ / -	(O-I-)\\(\(\(\(\(\(\)\)\)					= 6.5		
	(Sds)Wt/R		Sus -	1.028316	IX.	-0.5		
V =	0.1582025	(VVt)						
				<u>wxhx</u>				
<u>LvI</u>	Ht.	Wt.	wxhx	Totwxhx	<u>Fx</u>	V (total)	V(design)	
Eave	17.5			0.5993663	1,853			
						1 052	1 606	
Upper	9.5	9,992		0.3805413	1,176	1,853	1,686	
Main	5	1,002	5011.875	0.0200924	62	3,029	2,756	
Dana		10 520	249441.56	1	3,091	3,091	0	
Base		19,556	249441.50		3,091	3,031	o	
Tot Wt =	19,538 l	os						
V(base) =	3,091	os						
. (/								
O-n v 7E -	=1.3 x .7 E =.9	11 v E						
Design V =	0.91 E	=						
LvI	L (tot) v	(Design)						
Upper	22.25	76						
Oppor	22.20							

Uplift:

Main

30.88

89

Opini.							
	L(tot,used)	L1	Rup,1	L2	Rup,2	L3	Rup,3
Upper	22.25	16.25	310	6	497	0.0	606
Main	30.88	15.88	386	15	411	0.0	839

Client:

Mali McReynolds

Pacific City, Oregon Project:

By: Date: M.V.Nava 11/05/24

Line A

Seismic Calculations

A. 15. Light-frame (wood) walls sheathed w/wood structural panels rated for shear resistance

V = (Sds)Wt/R

Sds = 1.028316

6.5 R=

V = 0.1582 (Wt)

			1	<u>wxhx</u>			
LvI	Ht.	Wt.	wxhx	Totwxhx	<u>Fx</u>	V (total)	V(design)
Eave	17.5	13,051	228394.69	0.6932186	2,502		
Upper	9.5	10,640	101075.25	0.3067814	1,107	2,502	2,277
Main	0	1,377	0	0	0	3,609	3,284
							2004
		25,068	329469.94	1	3,609	3,609	3284

25,068 lbs Tot Wt = 3,609 lbs V(base) =

Q=p x .7E =1.3 x .7 E =.91 x E Design V = 0.91

LvI L (tot) v (Design) 569 Upper 4.00 4.00 821 Main

Unlift:

Opini.							
	L(tot,used)	L1	Rup,1	L2	Rup,2	L3	Rup,3
Upper	4.00	1.00	4535	0	4553	0	4553
Main	4.00	1.00	12313	0	12353	0	12353

Mali McReynolds

Pacific City, Oregon

By: Date: M.V.Nava 11/05/24

Line B

Seismic Calculations

A. 15. Light-frame (wood) walls sheathed w/wood structural panels

rated for shear resistance

V = (Sds)Wt/R

Sds = 1.028316

R= 6.5

V = 0.1582 (Wt)

wxhx

				VVIIX			
Lvl	<u>Ht.</u>	Wt.	wxhx	Totwxhx	<u>Fx</u>	V (total)	V(design)
Eave	17.5	20,585	360241.88	0.6686383	3,964		
Upper	9.5	18,792	178527.56	0.3313617	1,964	3,964	3,607
Main	0	1,802	0	0	0	5,928	5,395

41,180 538769.44 1 5,928 5,928 5395

Tot Wt = 41,180 lbs 5,928 lbs V(base) =

 $Q=p \times .7E = 1.3 \times .7 E = .91 \times E$ Design V = 0.91

Lvl L (tot) v (Design) Upper 8.50 424 8.50 635 Main

Linlift:

Opilit.							
	L(tot,used)	L1	Rup,1	L2	Rup,2	L3	Rup,3
Upper	8.50	8.50	3240	0	3395	0	3395
Main	8 50	8.50	9085	0	9425	0	9425

Mali McReynolds

Pacific City, Oregon

By: Date: M.V.Nava 11/05/24

Line C

Seismic Calculations

A. 15. Light-frame (wood) walls sheathed w/wood structural panels

rated for shear resistance

V = (Sds)Wt/R

Sds = 1.028316

R= 6.5

V = 0.1582 (Wt)

				<u>wxhx</u>			
Lvl	Ht.	Wt.	wxhx	Totwxhx	<u>Fx</u>	V (total)	V(design)
Eave	17.5	7,365	128887.5	0.5516097	1,533		
Upper	9.5	11,028	104769.56	0.4483903	1,246	1,533	1,395
Main	0	911	0	0	0	2,779	2,529
Base		19,305	233657.06	1	2,779	2,779	2529

Tot Wt = 19,305 lbsV(base) = 2,779 lbs

Q=p x .7E =1.3 x .7 E =.91 x E Design V = 0.91 E

Lvl L (tot) v (Design) Upper 12.00 116 Main 5.75 440

Uplift:

Opint.				2.2			D 0
	L(tot, used)	L1	Rup,1	L2	Rup,2	L3	Rup,3
Upper	12.00	6.00	821	3	875	0	930
Main	5.75	2.88	6005	0	6119	0	6119

Mali McReynolds Pacific City, Oregon By: Date: M.V.Nava 11/05/24

Roof DL	15	psf				
Lines : Upper Roof	1	2	3	Α	В	С
Trib Width Length	12.67 55.5	19.25 55.5	11.625 38	16.25 43.5	26.5 43.5	13 29
Lower Roof Trib Width Length	12.5 17		13.5 16		7.75 12.5	11.75 28.5
Upper Wall Trib # of walls	10.125 2	19.25 2	9.125 2	14.75 2	26.5 2	11.75 2
Wall Length # of walls	53 1	53 1	35 1	38.5 1	38.5 1	24 1
Main Wal Trib # of walls	12 2	19.25 2	7.25 2	14.75 2	25.25 2	10.5 2
Wall Length # of walls	53 1	53 1	35 1	38.5 1	38.5 1	24 1

	Mali McReynolds Pacific City, Oregon						By: Date:	M.V.Nava 11/05/24	
Upper Roof 2nd Wall	Wt 15 36	Line Qnty 703.185 73.25	1 Wt 10547.775 2637 1 3184.775	36	Line Qnty 1068.375 91.5	2 Wt 16025.625 3294 19319.625	36	Line Qnty 441.75 53.25	3 Wt 6626.25 1917 8543.25
Lower Roof 2nd Wall 2nd Floor 1st Wall	15 36 12 20.25	212.5 73.25 536.625 77	3187.5 2637 6439.5 1559.25 13823.25	36 20.25	91.5 1020.25 91.5	3294 12243 1852.875 17389.875	36 20.25	319.375	3240 1917 3832.5 1002.375 9991.875
1st Wall	20.25	77	1559.25	20.25	91.5	1852.875	20.25	49.5	1002.375
			1559.25			1852.875			1002.375

Client: Project:	Mali McReynolds Pacific City, Oregon					By: Date:	M.V.Nava 11/05/24	
	Wt	Line	Α	Line	В		Line	С
		Qnty	Wt	Qnty	VV t		Qnty	Wt
Upper Roo	f 15	706.875	10603.125	1152.75	17291.25		377	5655
2nd Wall	36	68	2448	91.5	3294		47.5	1710
			13051.125		20585.25			7365
Lower Roo	f 15			96.875	1453.125		334.875	5023.125
2nd Wall	36	68	2448	91.5	3294		47.5	1710
2nd Floor	12	567.875	6814.5	1020.25	12243		282	3384
1st Wall	20.25	68	1377	89	1802.25		45	911.25
			10639.5		18792.375	i		11028.375
1st Wall	20.25	68	1377	89	1802.25		45	911.25
			1377		1802.25			911.25

Client: Project:	Mali McReyno Pacific City, O					By: Date:	M.V.Nava 11/05/24			
Shear Walls	No.	Length	No.	Ĺ	ength.	No.	Length	No	Ler	ngth
A Upper	41			00		(0 0		00	
Main				00		(00		00	
В	1.0	-		00		,	00		00	
Upper	18.	0		00		,	30		00	
Main	1 8.	5		00		(0.0		00	
С										
Upper	16			23		(00		00	
Main	22.	875		00		(00		00	